


Arranging deck
Arrangement of beams for S.S. No 242.



Beams marked D.A. to be double angle steel, the one 6x3 1/2 the other 6x2 1/2
 All other beams single angle steel 6x3 1/2 from No 2 to No 38

Beams marked B.A. to be built iron 6x 1/2 and double angle 5x2 1/2
 D.A. to be double angle iron the one 6x3 1/2 the other 5x2 1/2
 All other beams single angle iron 6x3 1/2

Beams No 40 to 100 inclusive to be built steel 6x 1/2 with double angles 5x2 1/2

Arranging deck
Arrangement of beams for S.S. No 243.

S.S. "Kii Maru" Glasgow Report No 6595
 S.S. "Higo Maru" do do 6660

Beams marked D.A. to be double angle steel the one 6x3 1/2 the other 5x2 1/2
 All other beams single angle steel 6x3 1/2 from No 102 to 120

