

Barque "St Guthbert"
Glasgow Report No 6681.—

Rigging Plan of Barque No 330
& Particulars of Iron Spars

Spars	Length	Dia. Round	Plates in Round	Thickness Plates	Landings	Doubling plates & c
Bowsprit	22'	24 1/2	3	7/16 & 1/2	Double	
Foremast	14'-6"	14 1/2	3	7/16 & 1/2	Single	
Main Mast	16'-8"	24 1/2	3	7/16 & 1/2	Double	doubled at Wedging
Mizzen Mast	19'-3"	27 1/2	3	7/16 & 1/2	Double	" " "
Fore & Main Lower Yards	14'	14 1/2	2	3/16 & 7/16	Single	" at Sing
" " Lower Topsail	6-3"	15 1/2	2	7/16 to 1/2	Single	" " "

Note Butts all treble Riveted and Straps 1/4" thicker than plates
2 Angles inside of Lower & Topsail Yards in way of Slings
Angles & Diaphragm plate in Bowsprit

Scale 1/16 of inch = one foot

