

Lat. to Gls:
29/5/84.

Steel Screw Steamer No. 29.
Class 100 A.I.
Beale 1/2" = 1 Foot.
436

S.S. "Ross-gull"
Glasgow Report
No. 6760.



Anchor & Chains.
Numeral for Equipment - 5975.

2 Bowers	5 3/4	Out. or Stock
1 Stream	1 1/2	" "
1 Hedge	3/4	" "
165 Fathoms	1 1/2	Chain Cable
45 "	1 1/2	Stream chain
75 "	6 1/2	Towline
90 "	4	Hawser

Frames 3 x 2 1/2 x 7/16 spaced 21" apart centre to centre
Reverse Frames 2 1/2 x 2 1/2 x 7/32
Floor plates 12 x 5/16 x 6/16 in 8 x 10 space.
Bulkheads 4/16
Keel 7 x 1 5/8
Stern 6 1/4 x 1 5/8
Stern frame 6 1/4 x 3 1/4
Rudder head 3 3/4 dia. Keel 2 1/2 dia

Butt straps of Sheer Strake
Quarter & Main deck stringer plates
and 1 Strake at bilge to be 1/16
thicker than their plates & double
riveted for 1/2 length.