


Mr. D. G. L.  
12/5/84.

**MASTS**  
MAST PLATES OF STEEL, FOREN MAIN MASTS FITTED WITH ANGLE IRONS  
3/8" x 1/2" EXTENDING TO BOUNDS & LOWER MAST HEAD  
RIVETING LANDINGS TO BE DOUBLE RIVETED TO LOWER MAST  
HEAD. TOP MAST LANDINGS SINGLE RIVETED  
BUTT STRAPS TO BE FITTED INSIDE OF MAST & YACHT RIVETED  
TANGENT & 1/2" THICKER THAN THE PLATES THEY CONNECT  
FOREN MAIN MAST TO BE RIVETED WITH 3/8" RIVETS TO HEIGHT  
OF LOWER MAST HEAD. TOP MASTS TO BE RIVETED WITH 3/8" RIVETS  
MIZEN MAST BE RIVETED WITH 3/8" RIVETS

DIMENSIONS			
	FORE MAST	MAIN MAST	MIZEN MAST
DIMETER AT HEEL	22 1/2"	20"	20"
PARTNERS	30"	28"	20"
HOUNDS	24"	22"	20"
HEAD	28"	18 1/2"	17 1/2"
LENGTH FROM HEEL TO PARTNERS	33'-0"	23'-0"	15'-6"
PARTNERS TO HOUNDS	52'-0"	47'-0"	30'-6"
HOUNDS TO HEAD	4'-0"	9'-0"	7'-6"
LENGTH OF TOP MAST	22'-6"	28'-0"	18'-6"
TOPGALLANT MAST	14'-6"		
DIMETER AT JOE MAST HEAD	14"	8"	8"
OF TOP GALLANT MAST HEAD	8"		



No 222  
SCALE 1/2" = 1 FOOT  
MADE IN ENGLAND  
LONDON  
6 MAY 84  
CLYDE-BANK

J. D. Lake  
Superior  
Report No. 1905.

12/5/84