



SCALE 1"=1 FOOT. DRG No. 3761. 19<sup>TH</sup> APRIL 1889

80 lbs Working Pressure.  
332 Tubes - 57 Stay Tubes - 275 Plain Tubes.  
All Tubes 2 1/2" Ext. Dia. Steam spaces Stays 2 1/2" Dia.  
2 1/2" Screwed Steel. C.C. Stays 1 1/4" Screwed Steel  
nutted on both ends. All holes drilled  
Shell drilled to place.


The steel plate should be  
weakened in the stress  
or the longitudinal joint  
redesigned so as to have  
a percentage strength  
of not less than 78 of the  
solid plate

A.D.  
7.5.89.

*[Handwritten signature]*



S. S. "Lurenne" Glasgow Report No. 9648.-



*Handwritten signature/initials*



© 2021

Lloyd's Register  
Foundation

GLS217-0099