

No 8/T

MIDSHIP SECTION STEEL SHIP "YOLA"

SCALE 1/2 INCH = ONE FOOT

MOULDED DIMENSIONS - 220x38'6" x 24'-6"

LLOYDS DIMENSIONS - 218.58 x 38.5 x 25x29

CLASS - 100 A1

NUMERALS

1/2 BREADTH	19.25
1/2 DEPTH	25.29
1/2 GIRTH	40.22
1ST NUMERAL	81.76
2ND NUMERAL	218.58
	18526.84

PROPORTIONS

BREADTHS TO LENGTH = 567
DEPTHS TO LENGTH = 864

SCANTLINGS

FORECASTLE BEAMS BULB ANGLE 7x3 1/2 x 1/20
D² UNDER BOWSPRIT BULB 8x 1/20 ANGLE 3x3 x 1/20
POOP STRINGER 36 x 1/20 TO 25 x 1/20
POOP TIES - 10 x 1/20 TO 10 x 1/20
FORECASTLE STRINGERS 27 x 1/20 - 10 UNDER BOWSPRIT.
FORECASTLE TIES - 10 x 1/20
FORECASTLE STRINGER ANGLE - 3 1/2 x 3 x 1/20
POOP STRINGER ANGLE - 3 1/2 x 3 x 1/20
BREAST HOOKS 4x 1/20

