

Sent to Chief Surveyor 4.6.94.

Received from Chief Surveyor _____

VESSEL'S NAME

Im S.S. "Dorset"

Report

Gls. No. 12986

The remarks of the Chief Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.)

Nature of Survey

S.S. No. 3 Alterations

S.S.No. 3 due 5, 93 now held: awning deck partly renewed: tank top and 9 floors under boilers repaired: ceiling in part and bunker casings renewed, and screen bulkhead forming athwartship bunker has been ~~renewed~~ ^{removed} from before to abaft the boiler bulkhead, the side plates of bulkhead at original position being left forming web frames: the wood lower deck has now been removed between tie plates and stringers, and the vessel has now been remeasured for tonnage, the particulars of which are as stated on the report.

It is submitted the vessel appears worthy to remain classed 100A1 "part awning deck with freeboard," with record 5, 94 and notations of S.S. Gl's. No. 3-5, 94 and pt. N. D. 94.

The particulars in the Register Book of decks should be amended to 1 dkr (In. W.S.) + Awning dkr. (pt. in. W.S.) 2 tr. bms.

GLS 241-0081

100 A 1

"Awning dkr. with freeboard."

5, 94 Gl's.

S.S. Gl's. No. 3-5, 94

pt. N.D. 94

W. G. J.
4.6.94

Record of decks to be amended as above.



© 2021

Lloyd's Register Foundation