


List of Spare Gear
for
S.S. "Santo Domingo" N° 422
Engines. 28 $\frac{1}{2}$ - 48" - 74
 54"

Cylinders:-

- 1 H.P. Cylinder cover
- 1 H.P. Piston complete
- 1 Packing Ring for L.P. Piston
- 1 Packing Ring for I.P. Piston
- 1 Top liner and 1 bottom liner for Piston Valve
- 1 H.P. Piston Valve with rings and springs complete
- 1 set of Piston & Piston Valve springs

Rods, Spindles &c.

- 1 L.P. Piston Rod with nuts and splitpins
- 1 H.P. Valve Rod complete with collars, nuts, ^{bolts} and splitpins.
- 1 L.P. Valve Rod, to fit I.P. also, complete with collars, nuts, bolts and splitpins.
- 1 Complete set of brasses for one connecting rod
- 2 Crosshead shoes lined with white metal ready to put in place, to suit either engine.
- 2 Connecting Rod bolts, collar nuts, and splitpins. Top.
- 2 Connecting Rod bolts, collar nuts, and splitpins. Bottom.
- 2 Main Bearing Bolts with collar nuts.



Spare Gear N° 422 continued

Valve Gear &c.

- 1 Ahead Eccentric Rod, with brasses. Keeps and bolts, ready to put in place made to fit either engine.
1 Aft. do. do. do.
1 Malleable iron eccentric strap complete with bolts & white metal, to suit all positions in case of necessity except L. P. Ahead.
1 Malleable Iron Eccentric strap for L. P. Ahead, complete with white metal and bolts.
1 Eccentric Pulley in halves of forged & cast iron bolted together to suit all positions except L. P. Ahead in case of necessity
1 do. do. to suit L. P. Ahead only.
1 Gunmetal Quadrant block complete with 6 extra. brass slips.

Shafting &c.

$\frac{1}{3}$ rd crank shaft built.


1 Rymer for coupling bolts

1 set of coupling bolts with nuts & splitpins for one coupling.

1 Propeller Shaft, forged iron with nut and gunmetal liners
Propeller.

4 Propeller blades of steel

6 Propeller boss studs, Swedish iron with gunmetal nuts
and stopper pins.



© 2021

Lloyd's Register
continued
Foundation

GLS245 - 0053 1/4

Spare Gear No 422

Pumps.

- 1 Air Pump bucket with Muntz Metal rod, nuts
Studs, guards and valves complete.
1 Foot valves with guards, valves, studs, all complete
1 Head valve grating with guards, valves, studs & nuts complete.
1 Complete set metallic valves for Air Pump.
1 Circulating Pump bucket with muntz metal rods and
nut complete.

Spare Gear for Circulating Pump.

- 4 Gun metal gratings
4 Gunmetal guards for suction & discharge
2 Gunmetal bars for discharge Valves
2 Muntz metal bolts & nuts & copper split pins for the
gratings 1'-3" long.
2 do. do. 2 ft. 1" long.
2 do. do. 10 $\frac{1}{2}$ " long.
2 connecting links with brasses complete. & with bottom
crosshead and guide slippers to suit both Air. & Circ. Pumps
2 Links for crossheded end of pump levers complete
with brasses.

Sundries and Boiler mountings

Sundry bearings, brasses, valves, and seats
say 112 lbs. to be as follows. © 2021

- 2 stop valve spindles for 7" stopvalves on Main Boilers
1 do. do. 5" do. do.
1 spindle each for 3 $\frac{1}{2}$ ", 3", 2 $\frac{1}{2}$, + 2" stopvalves (4 in all)

Spare Gear N° 422.Sundries & Boiler Mountings (continued)

- 2 valves for stir values on pumps.
 24 sundry munts metal studs and bolts.
 50 condenser tubes
 200 Glands or ferrules for condenser tubes in a box
 40 Gauge glass tubes for main boilers & 10 for Donkey.
 1 set complete spare packing for high and Intermediate engines (Lindsay's)
 1 complete set of springs for safety valves and main escape valves.
 1 Safety valve spindle and seat.
 2 Valves & spindles for feed boiler chest.
 5 tons furnace bars for Main boiler
 12 cwts. do do. Donkey do
 1 set of bearers and fronts with doors for two furnaces
 Main boiler.
 20 Plain boiler tubes
 1 Half set embossed manhole doors with studs & bridges complete for one boiler
 10 cwts. assorted, finished and other bolts, nuts, & Setpins as may be selected $\frac{1}{2}$ " to $1\frac{1}{2}$ " dear.



© 2021

Lloyd's Register
Foundation