

4/11/87

# Staegoon

3<sup>rd</sup> October 1875

## James Lewis Sonnette

On the 5<sup>th</sup> July last examined the  
steel sc. I made for "Aileen" of Groen and  
325 tons gross registered while lying at anchor in  
Groenortland with a view of ascertaining the  
amount of damage alleged to have been sustained  
on the 15<sup>th</sup> May last by colliding with the S. S.  
"Ariadne" in the Alexandra dock at Liverpool.  
For further particulars please see log book.

Upon examination found the  
head of stern badly damaged, and the fore part slightly  
by on each side of forecastle damaged, the forward  
sternpost angle on each side slightly damaged and  
fractured; the furnishing plate on each side on  
forecastle head damaged together with the angle  
of forecastle of main deck slightly damaged also the  
bridge deck damaged; four rail stanchions and  
one at forward of forecastle head slightly. The  
bulk wood breast plate at upper part of stern being

The hawser glands recommended  
that it after inspection be repaired by welding and

a suitable compass and covering the upper part with  
forged pieces about four foot long; the plates  
on each side of foremast to be removed to  
facilitate repair of stem; slightly repaired a  
crooked part in side near stem, all fair and regular;  
the stronger angle on each side of foremast, to be  
repaired and casting of iron made good; the  
finishing plates on foremast head, to be removed  
and replaced, and the angle to be renewed, to be about  
twenty four feet; the maine angle on stem  
slightly repaired; the fore stay shott to be renewed  
also shott to maine; the fore foremast <sup>and</sup> shott  
and rails to be set fair and replaced; the same fore  
plate and upper part of stem to be renewed, and the maine  
also the repaired work to be painted and the vessel  
in all other respects to stand to the same good and  
official condition as she was to before she became  
disabled.

See £1.10.-  
~~Discount - 2.-~~  
~~£ - 10.-~~

H. Marrett.



© 2021

Lloyd's Register  
Foundation