

Str. to Gprk.
17/2/83.

MIDSHIP SECTION S.S. N° 7526

SCALE $\frac{1}{2}$ INCH = 1 FOOT.

CLAS 100 A.

| | |
|----------------|----------|
| Depth | 17.5 |
| Half Breadth | 16.0 |
| Half Girth | 30.3 |
| First Numerai | 63.8 |
| Length | 234.8 |
| | 51.04 |
| | 25.52 |
| | 12.76 |
| second Numerai | 1498.024 |
| add to 1st | 1498.02 |
| Equip. Numerai | 16478.26 |

| | |
|-----------------------|------|
| Positions | |
| Breadth to Length | 7.33 |
| Depth to Length | 13.4 |
| Numerai at Quad. Deck | 69.8 |

| EQUIPMENT | |
|-----------------|-------------------------------|
| 2 Bower Anchors | 21 cwt. ex Stock (Collective) |
| 1 Stream | 18 " |
| 1 Hodge | 3 " |
| 240 Fathoms | 1 " Stud Chain Cable |
| 75 " | 1 " Stream Chain |
| 90 " | 10 " Towing |
| 90 " | 8 " Haver |
| 90 " | 5 " Wavy |

Note. Scantling for Raised Deck shown in Aid.
Frames all to Gunwale of Deck.
Reverse Frames to Hold Stringer + Beam Stringer alternately.
Sides of Deck increased to in way of Deck.
Butt Straps at sides of Deck Sheet Straps + Straps next below.
to thicker and truss riveted in way of Deck.
Main Stringer to extend T-frame spaces into Deck.
Deck Stringer + Frames below Deck. Main Stringer to
overlie Main Stringer about 16 feet.

S.S. "Cassia" + "Claudia"
Greenock Report No 8585 and
No 8631

