

LLOYD'S REGISTER OF SHIPBUILDERS  
 LONDON  
 2 APR. 84  
 LLOYD'S REGISTER OF SHIPBUILDERS  
 LONDON  
 2 APR. 84  
 LLOYD'S REGISTER OF SHIPBUILDERS  
 LONDON  
 2 APR. 84

Str. to Gnr.  
 44/84  
 15/5/84  
 4/6/84

area of tube to be  
 equal to or over  
 bottom of channel.

18/6  
 3/4/84

ship General Roberts  
 Greenock Rept. No. 8750

Standing Rigging to be of White Cross B. B. wire rope.  
 Fore, Main, Mizzen Lower Shrouds & Cap  
 Topmast back Stays } 5" = 4 1/2" Steel  
 Topgallant back Stays } 3 1/2" = 3" Steel  
 Lower & Topmast Stays } 5" double, Topmast Stays 4 1/2" = 4 1/2" Steel  
 Topgallant Stays } 3 1/2" = 3" Steel  
 Chain plates } 1 1/2" = 1 1/2" Steel  
 Sigger Lower Shrouds & Topmast back Stays } 3 1/2" = 3 1/2" Steel  
 Topgallant back Stays } 2 1/2" = 2 1/4" Steel  
 Lower Stay } 1" single = 3 1/2" Steel  
 Topgallant Stay } 2 1/4" = 2 1/2" Steel  
 Chain plates } 1 1/2" = 1 1/2" Steel  
 Inner bob stay bar } 3 1/2" pin 2 1/2"  
 Outer bob stay bar } 2" pin 1 1/2"  
 Double bowsprit shrouds } 4"  
 Fore, Main & Mizzen Mast 86' 4" x 30" to have 3 plates in round,  
 with 3 internal angles 3 1/2" x 3 1/2" plating 1/4" to 1/2"  
 Sigger Mast 83' 10" x 24" plating 1/4" to 1/2"  
 Bowsprit 22' 9" to 24' 28" diam. in Knighthead, plating 1/4" to 1/2"  
 angles 4" x 3" 7/16"


RIGGING PLAN 18106.  
 SCALE 1/2 INCH ONE FOOT.

Tonnage under deck abt 1830

RUSSELL & CO.  
 SHIP BUILDERS  
 18 MAR. 84  
 PORT-GLASGOW & GREENOCK



Rigging Plan.



© 2020

Lloyd's Register  
Foundation