



All lands of Fore Mast and Bowsprit 4 1/2 x 2 7/8 1/2 rivets
 Butts above deck and from 11 1/2 to bowsprit cap 7 1/2 x 3 7/8
 " below " " outside of stay cap + inside 11 1/2 x 3 7/8
 Fore Mast 2 plates in the round
 Bowsprit 2 plates in the round with 2 angles 3 1/2 x 3 1/2 1/2 rivets
 cap. Main Trizen and Jigger Mast
 Lands of Masts 4 1/2 and 2 7/8 1/2 rivets
 Butts " " above deck 7 1/2 and 3 7/8
 " " below " 5 " 2 7/8
 Masts 2 plates in the round
 Yards and Topmasts
 Lands of Yards and Topmast 2 1/4 single riveted
 Butts capped 7 1/2 x 3 7/8
 Butts of Topmasts in way of topmast yards stepped
 Straps to blocks 1 3/8
 2 Angles 3 x 2 1/2 1/2 in foremast

Nestfield

RIGGING PLAN

N^o 390

Scale 1/8 inch = one foot
 Under Deck Formage 1020



