

TELEPHONE NO. 11
WIRE, GALVANIZING WORKS
GRAPHIC ADDRESS

GRAPHIC ADDRESS
"WIRE" WARRINGTON.
TELEPHONE No. 11.



WIRE MILLS, WIRE ROPE,
WIRE NETTING.
& GALVANIZING WORKS.

From Rylands Brothers, Limited,

Warrington Jan. 4th 1897

Certificate for Steel Wire Rigging.

We hereby Certify, that the $702\frac{2}{3}$ fathoms of
 $4\frac{1}{2}$ inch circumference galvanized Steel Wire Rigging
supplied to Mess^{rs} W. Hamilton & Co.,
for their boat ~~SE~~ IV^o 129. is
composed of 6 strands, each containing 7 wires of .160 inch
diameter, and that the several wires, after being galvanized, have
been subjected to, and have successfully withstood, the following
tests, viz. —

Each wire has withstood a tensile stress at least equivalent to that
set forth in Table No. 11, of the Rules of Lloyd's Register
of Shipping, and the aggregate strength of the wires is
not less than 10 per cent. in excess of that stress.

Each wire has been twisted eight times round itself as a core,
and untwisted again and straightened without fracture.
No hemp has been used in the strands, a hemp core only being fitted.

We guarantee that the Steel Wire Rigging of
 $4\frac{1}{2}$ inches in circumference above described will bear a strain
of 38 tons without breaking.

for Rylands Brothers, Limited.

W. I. Hulme

Secretary.

ARW337-0071