

# CERTIFICATE FOR STEEL WIRE RIGGING.

We hereby Certify that the 1511 ~~feet~~ fathoms of  
 $3\frac{1}{8}$  inch circumference galvanized Steel Wire Rigging  
supplied to Messrs A Weir & Co.  
for the "Bedarban" is  
composed of 6 strands, each containing 7 wires of .109 inch  
diameter, and that the several wires, after being galvanized, have  
been subjected to, and have successfully withstood, the following  
tests, viz.:

Each wire has withstood a tensile stress at least equivalent to that set forth in Table No. 11 of the Rules of Lloyd's Register of Shipping, and the aggregate strength of the wires is not less than 10 per cent. in excess of that stress.

Each wire has been twisted eight times round itself as a core, and untwisted again and straightened without fracture.

No hemp has been used in the strands, a hemp core only being fitted.

We guarantee that the Steel Wire Rigging of  
 $3\frac{1}{8}$  inches in circumference above described will bear a strain of  $17\frac{1}{2}$  tons without breaking.

R. S. NEWALL & SON, LTD.

R. S. NEWALL & SON, LTD.,

19 EXCHANGE SQUARE,

GLASGOW.

Pited Service  
Manufactured.

17<sup>th</sup> Augt-97

GRK 338 - 0155

