

"Gederbank." Block List.

Greenock Reg. No 11813.

N ^o	Kind	Size	Pushes	Purpose	Strapping
6	S	16	S. M.	Fore main & mizen lower brace	Shackle eye & Becket
6	"	16	"	" " " " "	Shackle eye or bows with bullseye for lead
4	"	15	"	Fore & main lower brace leads	Swivel cleats on main rail
2	"	15	"	Mizen lower brace leads on bumphins	" "
6	D	11	P	Fore main & mizen lower clew garnets	Swivel hooks
6	S	10	"	" " " " "	Clip hooks
6	"	10	"	" " " " " leads	Swivel hooks
6	D	10	S.	" " " reef tackles.	Clip hooks
6	S	10	"	" " " " " "	" "
6	"	9	"	" " " " " leads	Swivel hooks
6	D	10	"	" " " buntlines	" "
12	S	9	"	" " " whips	Wire Strop
12	"	8	"	" " " leads on yards	" "
6	D	8	"	" " " leechnines.	Swivel hooks
12	S	8	"	" " " " "	Wire Strop
6	D	10	"	" " " lifts	Clip hook & Becket
6	"	10	"	" " " " "	Swivel hook
10	S	11	"	" " " tacks & sheets	Clip hook (round block).
6	"	"	"	outside strop	
6	"	9	"	" " " topsail lifts	Clip hook & Becket
6	"	9	"	" " " " " "	Swivel hook
6	"	15	P	" " " " " braces	Bow
6	"	13	"	" " " " " whips	Bow or shackle eye
4	"	13	"	Fore & main lower topsail leads on rails	Swivel cleats on main rail
2	"	13	"	Mizen lower topsail leads on bumphins	" "
12	"	10	"	Fore main & mizen lower topsail clewlines	Clip hook & metal sheaves
6	"	9	"	" " " " " whips	" & becket
6	"	9	"	" " " " " leads	Swivel hooks
6	D	9	P.	" " " " buntlines	" "
12	S	8	S.	" " " " leads on yards	Wire Strop
2				Heavy Purchase blocks	



GRK338-0165 (1/2)

(2)

N ^o	Kind	Size	Pushes	Purpose	Stropping
6	S	15	P	Fore main & mizen upper topsail braces	Shackle eye
6	"	13	"	" " " " " whips	" "
4	"	13	"	" & " upper topsail leads on rail	Swivel hook on swivel cleat on main rail
2	"	13	"	Mizen upper topsail leads on buntlines	Swivel cleats
6	D	10	P	Fore main & mizen upper topsail sheet	Bow & becket
6	S	10	"	" " " " " "	Swivel hook
12	"	9	"	" " " " " reef tackles	Clip hook
6	"	9	"	" " " " " whips	" " or bow
6	D	9	P	" " " " " buntlines	Swivel hook
12	S	8	P	" " " " " leadson yards	Wire stop
3	S	17	P	" " " " " topsail halyards	Shackle eye & becket
				inside plate outside stop	
3	"	17	"	" " " " " " " " "	Swivel hook
3	S	16	P	Fore main & mizen upper topsail leads	" "
12	"	9	"	" " " lower topgallant clewlines	Cliphooks metal sheaves
6	"	8	"	" " " " " whips	Cliphooks
6	D	9	"	" " " " " quarter blocks	Swivel hooks
3	"	8	P	" " " " " buntlines	" "
6	S	7	P	" " " " " leadson yards	Wire stop
6	"	7	P	" " " " " leechnines	Swivel hook
6	"	7	"	" " " " " leadson yards	Wire stop
6	"	9	"	" " " " " sheets	Bow
6	"	11	P	" " " " " braces	Swivel hook
6	"	10	P	" " " " " whips	Bow & Shackle
3	S	14	"	" " " upper topgallant halyards	Shackle eye
				inside plate outside stop	
3	S	14	"	" " " " "	Swivel hook
3	S	12	"	" " " upper topgallant leads	" "
6	"	8	"	" " " " " downhauls	Cliphooks metal sheaves
6	"	8	"	" " " " " whips	Cliphooks
6	D	9	"	" " " " " quarter blocks	Swivel hooks metal sheaves
3	"	8	"	" " " " " buntlines	Swivel
6	S	7	P	" " " " " leadson yards	Wire stop



(3)

N ^o	Kind	Size	Pushes	Purpose	Stropping
6	S	11	P	Fore main & mizen upper topgallant braces	Swivel
6	"	10	"	" " " " " " " whips	Bow
6	"	8	P	" " " " " " " Sheets	"
3	S	11	P	" " " " " royal halyards	Cliphook & becket
3	D	11	"	" " " " " " "	Swivel hook
3	S	10	"	" " " " " " " leads	" "
6	S	8	"	" " " " " " " braces	Cliphook & becket
6	"	8	"	" " " " " " " whips	"
12	"	8	"	" " " " " " " Clewlines	Cliphooks
6	"	8	"	" " " " " " " quarter blocks	" metal sheaves
3	D	8	P	" " " " " " " buntlines	(Stope stop) wire
6	S	6	P	" " " " " " " leadson yards for buntlines	Wire stop
6	"	6	"	" " " " " " " leechnines	" "
6	"	6	"	" " " " " " " leadson yards	" "
6	"	7	"	" " " " " " " Sheet whips	Bow
1	D	11	P	Inner jib & topmast staysail halyard	Swivel hook
				Galvd. sheaves, brass roller bushes	
2	S	9	"	Inner jib & topmast staysail whips	Shackle eye
2	"	9	"	" " " " " " " downhauls	Wire stop
4	"	10	P	" " " " " " " sheets	Round blocks
1	"	11	P	Outer jib halyards. Galvd. sheaves, brass roller bushes	Swivel hooks
1	"	9	"	" " " " " " " whips	Bow eye
1	"	9	"	" " " " " " " downhauls	Cliphook, wire stop
1	"	9	"	" " " " " " " leads	Swivel hook
2	"	10	"	" " " " " " " sheets	Wire stop round block
2	"	8	"	Flying jib halyards Galvd. sheaves, brass roller bushes	Wire stop
2	"	7	"	" " " " " " " whips & downhauls	" "
2	"	9	"	" " " " " " " sheets	Wire stop round block
2	"	11	"	Main & mizen topmast staysail halyards	Swivel hooks
				Galvd. sheaves, brass roller bushes	
2	"	9	"	Main & mizen topmast staysail whips	Shackle eye
2	"	9	"	" " " " " " " leads	Swivel hooks
2	"	8	P	" " " " " " " downhauls	Wire stop



(4)

No	Kind	Size	Bushes	Purpose	Stropping
2	S	8	P	Main & mizen topmast staysail tripping knees	Wire stropped
2	"	9	"	" " " " sheets	Round blocks of be
2	"	9	"	" " " " " "	spliced into pendants
1	"	8	"	Jigger topmast staysail halyards. Galld. sheaves.	Swivel hooks
1	"	7	"	" " " " whips	Shackle eye
1	"	7	"	" " " " downhauls	Wire stropped
1	"	7	"	" " " " tripping lines	" "
1	"	8	"	" " " " sheets	Wire stop round blocks
1	"	8	"	" " " " " "	Swivel hook
2	"	9	"	Main & mizen t'gal't staysail halyards whips Galld. sheaves, brass roller bushes.	Cliphook
2	"	9	"	Main & mizen t'gal't staysail halyards whips	Shackle eye
2	"	8	"	" " " " " " leads	Swivel hooks
2	"	7	P	" " " " " " downhauls.	Wire stropped
2	"	7	"	" " " " " " tripping lines	" "
2	"	8	"	" " " " " " sheets	" " round block.
2	"	8	"	" " " " " " " "	Swivel hooks
1	"	7	P	Jigger topgallant staysail halyards.	Metal sheaves. wire stop
2	"	6	"	" " " " " " whips & downhauls	Wire stropped
1	"	6	"	" " " " " " tripping lines	" "
1	"	7	"	" " " " " " sheets	Round blocks
2	"	8	"	Jigger staysail halyards	Clip hooks
1	"	8	"	" " " " " " downhauls	Wire stop
1	"	8	"	" " " " " " tripping lines	" "
1	D	9	C.	" " " " " " sheets	" " Cliphooks
1	S	9	"	" " " " " " " "	Swivel hook
2	D	8	"	Spanker vangs	Clip hook.
2	S	8	"	" " " " " " " "	Swivel & becket
8	"	4	P	" " " " " " " " brails	Bows
1	"	9	"	" " " " " " " " head outhaul	Shackle eye & becket
1	"	9	"	" " " " " " " " " "	Swivel hook
1	"	8	"	" " " " " " " " tripping line	" "



Greenock Report No 11813.

(5)

No	Kind	Size	Bushes	Purpose	Stropping
2	S	9	P	Spanker foot outhaul. metal sheave in boom end	Clip hook, round block metal sheaves
1	"	9	"	" downhauls.	Swivel hook
1	D	9	"	" "	Clip hooks
1	"	5	"	" gaff end block.	Iron block galv'd.
2	"	11	"	" boom sheets	As may be arranged
2	S	8	"	" quarter guys	Clip hooks
2	"	8	"	" " "	Swivel hooks
2	"	9	"	Gaff topsail halyards.	Shackle eye & becket
2	"	6	"	" " downhauls.	Wire stropped
2	"	8	C	" " tacks. Spliced into standing parts for whip	" "
1	"	8	P	" " tripping lines	" "
1	D	8	C	" " sheets. Part chain. metal sheave in gaff end	Swivel hook.
4	S	11	P	Boat tackles.	To fit davit & becket
4	D	11	"	Boat tackles	hook & link
2	D	10	"	Relieving tackles	hook & becket
2	S	10	"	" "	Swivel hook
2	D	15	G.M.	Luff tackles, inside plated	Wire stop & hook
2	S	15	"	" " " "	" " "
2	D	14	"	" " " "	" " "
2	S	14	"	" " " "	" " "
2	D	10	P	Watch tackles.	" " "
2	S	10	"	" " " "	" " "
1	D	8	"	" " " "	" " "
1	S	8	"	" " " "	" " "
4	D	11	G.M.	Main & Crossjack tack tackles	Rolling hook & becket
4	S	11	"	" " " "	" " "
30	S	4 1/2	P	Leading trucks for rigging	" " "
38	D	4 1/2	"	" " " "	" " "
18	"	4	"	" " " "	" " "
30	"	3	"	Bullseyes	" " "



(6)

Blocks on all yards for buntlines and leeclines instead of bullseyes. Mast hoops for jigger topmast, 2 top blocks approved, 3 iron snatch blocks, 2 tail blocks. All blocks to be properly riveted with square nail rivets on washers. All blocks and blockwork to be full sized. Sheaves where not iron to be lignumvitae. All cast iron sheaves where used for brace and halyard block to be galvanized with patent roller or gunmetal bushes.

Blocks to be stropped inside and outside where required. Boat davit blocks to have patent roller bushes, all huff tackle blocks to have gunmetal bushes and steel pins. Fairleads on tops and cross trees as required for running gear. Spare blocks to be finished and sizes as required.

All iron ginn blocks for lifts, halyards, sheets, etc, to be supplied where required.



© 2021

Lloyd's Register
Foundation

