



Masts & Spars "Cedarbank"

Scale 1/2 inch = 1 Foot

Fore & Mizzen Lower Masts 2 Plates in the round all lands
4 1/2" broad & 2 R. 3/4 Rivets. Butts lapped 5" & 2 R. below deck
7 1/2" & 2 R. above deck, 4 Angles 4" x 3" & 3/4" whole length

Topmasts

2 Plates in the round all lands 2 1/2" broad S.R. 3/4 Rivets
Butts lapped 7 1/2" S.R. Butts strapped in way of Toprail Yards
Straps to be thicker than plates they connect.
2 Angles 3 1/2" x 3" & 3/4"

Yards

Landings 2 1/4" broad S.R. 3/4 Rivets
Butts lapped 7 1/2" S.R.

Topgallant & Masts

Landings 2 1/4" broad S.R. 3/4 Rivets