


# (LLOYDS REGISTER.)

G. R. 130  
Lloyds.

## VESSELS OF 100 TONS AND UPWARDS.

Particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyds Register of British and Foreign Shipping.

(if any) P.W.V.D.



Number.	Name of Ship.		No., Date, and Port of Registry.	
30	"Craigoowan"		1/1898 Leith	
Port of Previous Registry (if any).				
Whether a Sailing or Steam Ship; and if a Steam Ship how propelled	Where Built.	When Built.	Name and Address of Builders.	
Steam Screw	Port Glasgow	1898	A. Rodgers & Co., Port Glasgow.	
Decks	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post	Feet.	Tenths.	
Two	...	314	4	
Schooner	Length at quarter of depth from top of weather deck at side amidships to bottom of keel	314	-	
elliptical	Main breadth to outside of plank	44	-	
clinchers	Depth in hold from tonnage deck to ceiling at midships	20	75	
none	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards	-	-	
none	Depth from top of beam amidships to top of keel	24	12	
steel	Depth from top of deck at side amidships to bottom of keel	23	42	
five	Round of beam	-	84	
five double	Length of engine room (if any)	42	-	
bottom raft peak 6.4 tons				

### PARTICULARS OF DISPLACEMENT.

Water the depth from weather deck to bottom of keel	5463 tons.	Ditto per inch immersion at same depth	27 tons.
---	------------	--	----------

### PARTICULARS OF ENGINES (if any).

Description.	Whether British or Foreign made.	When made.	Name and Address of Makers.	No. of and Diameter of Cylinders.	Length of Stroke.	N. H. P. I. H. P. Speed of Ship.
Engines.	British	Engines.	Hall Brown Buttery & Co Govan.	Three 22 1/2"	42"	249 1000
Boilers.		Boilers.	A. & J. Inglis, Glasgow.	34" 61"		9 knots
Expansion						
Two steel		1898				
when loaded 160 lbs.						

### PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Deck	2373.84	On account of space required for propelling power	802.35
Spaces above the Tonnage Deck, if any		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	
Spaces between Decks	39.85	These spaces are the following, viz.:-	
Use	33.02	Upper Forecastle	
Enclosed-in spaces, if any, as follows:-	20.01	Bridge Side houses house on Bridge	61.48
Houses	34.21	S. 49 Act 1894	
Way excess for Light & Air	6.40	Chart house 3.24	
		Bosns store 23.36	
Gross Tonnage	2507.33	Masters Room 4.41	34.35
As per Contra	898.18	Masters Bath etc. 3.34	
Registered Tonnage	1609.15	Total Deductions	898.18
		Cubic Metres.	
		7095.74	
		2541.85	
		4553.89	

Name of Master	Certificate of { Service No. Competency No.
----------------	---

One  
Name, and Description of Managing Owner if there are more owners than one.  
Scottish Oceanic Steamship Company Limited,  
13 Bernard Street, Leith, County of Edinburgh.  
James Russell, of the same address. Manager.  
February 1898

