

## CERTIFICATE FOR STEEL WIRE RIGGING.

We hereby Certify that the fathoms of  $3\frac{1}{4}$  inch circumference galvanized Steel Wire Rigging supplied to Mess Russell & Sons Glasgow for the Ship No 457 S.S. Florida is composed of six strands, each containing seven wires of .115 inch diameter, and that the several wires, after being galvanized, have been subjected to, and have successfully withstood, the following tests, viz.:

Each wire has withstood a tensile stress at least equivalent to that set forth in Table No. 11 of the Rules of Lloyd's Register of Shipping, and the aggregate strength of the wires is not less than 10 per cent. in excess of that stress.

Each wire has been twisted eight times round itself as a core, and untwisted again and straightened without fracture.

No hemp has been used in the strands, a hemp core only being fitted.

We guarantee that the Steel Wire Rigging of  $3\frac{1}{4}$  inches in circumference above described will bear a strain of Nineteen tons without breaking.

Warrington

May 18. 1900



© 2019

Hloyd's Register  
Foundation

GRK 352-0219

6035705  
Wue Riggay



© 2019  
Lloyd's Register  
Foundation