

S.S. "ITONUS" ex "ANGLIA".

A detailed sketch showing a proposed lengthening of No. 3 hatchway was submitted and approved on the 16th instant, when the Builders proposed to fit doubling plates at the corners of the extended hatchways.

They now find that this involves considerable interference with the wood deck in order to procure the shift of butts, and a sketch showing an alternative arrangement in lieu of doubling plates on the deck at the hatchway corners has been handed in by Mr. Millar, the Builders' representative, with whom the arrangement has been discussed.

It is submitted that provided a plate be fitted below as proposed, and a ⁶ 5" x ⁶ 5" x 10/20" angle be fitted round the corners as indicated on the sketch, the same will merit approval, and the Surveyors should be informed accordingly.

C.B.

31.10.07.

[Handwritten signature]

Dr. Gerk 3/10/07
1 plan.



© 2020

Lloyd's Register
Foundation

GER 355-0104