

S. S. "SOLGLIMT".

It is submitted the Gothenburg Surveyors be informed that it is considered the plating of the Whale Dock should be adequately stiffened, especially as this forms part of the watertight subdivision of the vessel.

If desired the Whale Dock may be stiffened longitudinally with bulb angles $10" \times 3\frac{1}{2}'' \times .56"$, spaced 3 feet apart. These stiffeners should be bracketed to the watertight bulkheads, and should pass continuously through the other transverse members.

Wire:-

"Solglimit Whale Dock should be adequately stiffened.
"Longitudinal stiffeners $10" \times 3\frac{1}{2}'' \times .56"$ bulb angles
"or equivalent spaced three feet apart could be approved.
"Writing".

sd. 16/3/29
sd. (2d. Attn.) 9/3/29.

M. H. W. S. *OK*
19. 3. 29.



© 2021

Lloyd's Register
Foundation

HAMIL22-0200