

(LLOYDS REGISTER.)

G. R. 130
Lloyds.

VESSELS OF 100 TONS AND UPWARDS.

*** These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyds Register of British and Foreign Shipping.

Signal Letters (if any)

Official Number.	Name of Ship.	No., Date, and Port of Registry.		
102728	Verbena	7 th in 1895. West Hartlepool.		
No., Date, and Port of Previous Registry (if any). Nil				
Whether British or Foreign Built.	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled	Where Built.	When Built.	Name and Address of Builders.
British	Steam screw	West Hartlepool Durham	1895	Furness withy & Co. Ltd. West Hartlepool.
Number of Decks	One or break	Length from fore part of stem, under the bowsprit to the aft side of the head of the stern post	Feet.	Tenths.
Number of Masts	Two		293	
Rigged	Schooner	Length at quarter of depth from top of weather deck at side amidships to bottom of keel	293	
Stern	Elliptic	Main breadth to outside of plank	41	6
Build	Blucher	Depth in hold from tonnage deck to ceiling at midships	17	
Galleries	None	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards	20	8
Head	None	Depth from top of beam amidships to top of keel	20	1
Framework and description of vessel	Steel	Round of beam	42	9
Number of Bulkheads	Six	Length of engine room (if any)		
Number of water ballast tanks, and their capacity in tons	Five 440 tons			

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck } 3990 tons.
at side amidships to bottom of keel } Ditto per inch immersion at same depth } 24.8 tons.

PARTICULARS OF ENGINES (if any).

No. of Engines	Description.	Whether British or Foreign made.	When made.	Name and Address of Makers.	No. of and Diameter of Cylinders.	Length of Stroke.	N. H. P. I. H. P. Speed of Ship.
One	Compound Triple Expansion Direct Acting Inverted Cylinders Surface Condensing Boilers.	British	1895	J. Richardson & Sons. Ltd. Hartlepool	Three 22" 35" 59"	39"	224 800 8 1/2 Knots.
	Number		1895				
	Iron or Steel						
	Pressure when loaded						

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck	1771.73	On account of space required for propelling power	456.35
Closed-in spaces above the Tonnage Deck, if any		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	
Space or spaces between Decks	164.66	These spaces are the following, viz.:-	
Poor Break	357.09	Forecastle	54.41
Forecastle	41.11	Round House	16.68
Round House	23.74		
Other closed-in spaces, if any, as follows:-	5.26		
Hatchways excess			
Water Tanks			
Gross Tonnage	2363.59	Cubic Metres.	
Deductions, as per Contra	859.01	Masters Room 9.08	
Registered Tonnage	1504.58	Chart Room 4.59	31.24
		Boys's Store 14.60	
		Total Deductions	859.01

Name of Master Thomas Owen

Certificate of { Service No. 99658
Competency No.

No. of Owners One

Name, Residence, and Description of Managing Owner if there are more owners than one.

Verbena Steam Ship Co. Ltd.
West Hartlepool, County of Durham.

Jesse Lilly, same address, is manager

19 April 1895