

Half Section of Schooner to class 8 years A 1
Kiel 80 ft. Fore rake 4 ft. Beam 21 ft. Depth - 9-9

Sept 100 Lons, building at Burton Station
by Mrs Wrayton Rec. 24/3/68

Beams amide ships 9×9

Beams Waterways, Gunwales
Wales & Top sides English Oak,
The whole of timbers of frame Oak,
Kelson & sides, Greenheart,
To be wood lodging, Kased with Oak
throughout - & to have
5 pairs of long iron side knees
to take two bolts in floor heads

Register Tonnage
100

111
 33.3.69

Scale ²/_{yr}
Gard 1

© 2021

Building at
Lloyd's Register
Foundation

HVL 394-0173