

LENGTH Feet. Inches. Main Deck ditto hull

Lloyd's Register of British & Foreign Shipping.

Liverpool

13th Aug^r 1883.



must bear only the signature of Surveyors to Lloyd's Register of Shipping.

This is to Certify that
H. Moverly the
undersigned Surveyor to this Society did at the
request of Mr. D. P. Garbutt survey
the Iron Masts constructed at this
Port by Messrs. Galt & Smith Jun^r &
Co^s, for the S. S. "Bell Rock", of the
following dimensions; viz, Fore Mast
80 ft 6 ins long, Main Mast 74 ft long.
Diam^s 24 1/2 & 23 ins respectively, Plates
in foremast 7/16 to 5/16, doubled in way of
wedging with plates 8 ft long by 7/16 thick.
3 longitudinal angles fitted each 3 1/2 x 2 1/2 x 6/16.
Main Mast plates 6/16 to 5/16, doubling plate 8 ft
by 6/16; angles 3 1/2 x 2 1/2 x 6/16 full length of mast.
Masts formed with two plates in the round
stems lapped single riveted, butts lapped
and treble riveted. The workmanship
and material good. —

H. Moverly.

Dec 2. 2. 0



Lloyd's Register
HUL 396 0086
Foundation