

S. S. Rosario

Registered Dimensions: $275.3 \times 34.3 \times 19.2$

Tonnage under deck: 1403

Coefficient of Fineness: .79

Unmolded depth 21 ft 1 in.

Freeboard per Tables A

add for deficient sheer $\frac{41-37}{4}$

ft in

4 .. 1

1

4 .. 2

deduct for erections P. 176 ft, F. 29 1/2 ft

1 .. 3

2 .. 11

deduct for extent of rim & freeboard
covered by erections & freeboard
being measured to that deck

2 1/2

2 .. 8 1/2

add for extreme proportions }
13 depths

1 1/2

2 .. 10

add for winter months in
North Atlantic }

8

Freeboard 3 ft 6 in



© 2020

Lloyd's Register
Foundation

1884.

Ball: 10 Mar.

Mr. McNeil.

S.S. Rosario.



© 2020

Lloyd's Register
Foundation