

22. X. 97

*Admiral  
Hull Report No 11390.*

# S.S. No 209 MIDSHIP SECTION

SCALE.  $\frac{1}{2}$  INCH TO ONE FOOT

112' 0" x 21' 0" x 11' 6" HOLD

## DIMENSIONS

LENGTH AS PER RULE 110' 10"

HALF MLD. BREADTH 10' 5"

DEPTH KEEL TO M.D.B. 12' 10"

*Depth moulded 12' 3 1/2"*

1/2 BREADTH 10' 4 1/2"

1/2 GIRTH 18' 2 1/2"

DEPTH 12' 8 3/4"

1ST N° 41' 53"

110' 87"

220' 71"

332' 24"

415' 30"

415' 3"

2ND N° 4604' 4311"

RAISED QUARTER DECK.

CLASS 100A1.

BEAMS 5x3 x 1/16 OR ALTERNATE FRAMES

FRAMES 3x2 1/2 x 1/16 SPACED 20 APART

REVD 2 1/2 x 2 1/2 x 1/16 TO STRINGER & DECK ALTERNATELY.

IN WAY OF HOLD & DOUBLE IN E. & B. SPACE.

FLOORS 10' x 1/16 TO 1/16 & 1/16 IN E. & B. SPACE.

BULKHEADS 4' 1/16.

KEEL & STEM 7 1/2" x 1 1/8" (BULB).

STERN POST 6" x 2 1/2".

RUDDER HEAD 3 1/2". HEEL 2 1/4".

T IRON STANCHION 6" x 3" x 1/16 IN THWART BUNKER.

STANCHIONS 2 1/2" DIA. IN HOLD.

COCHRANE & COOPER  
IRON & STEEL SHIPBUILDERS  
BEVERLEY

TRACING No 648.

20/7/97.



LOYD REGISTERED  
ARCHIVED  
22 JUL 91  
LOND N 4

209

~~s/s Admiral~~  
~~Hull Report No. 11390.~~



mb D 22

© 1992

91142(1)11

SCALE 1/2 INCH

0 13 0 511

*[Faint, illegible markings]*

© 2019

Lloyd's Register  
Foundation