

No. 356 Survey held at Narviel Date 8 November 1854
on the Ship, Narviel Master George Franklin
Tonnage Old 620 Tons Built at Narviel When built 1854 Launched 1854
By whom built John Dany Owners Brown & Co
Port belonging to London Destined Voyage Narviel to London
If Surveyed while Building, Afloat, or in Dry Dock While Building

Length aloft	Feet.	Inches.	Extreme Breadth Outside'					Feet.	Inches.	Depth of Hold		Feet.	Inches.
	151-	7/10						28-	7/10-			19	-
Scantlings of Timber.													
TIMBER AND SPACE													
Floors	30	30 3/4						Outside.		INCHES.		Inside.	
1st Foothooks	13 1/2	13 1/4	15	11	13 1/2	10	Garboard Strakes ..	4	4	Limber Strakes	4 1/2	4 1/4	
2nd Ditto	11 1/2	11 1/2	11	9 1/2	11	9	Garboard to Bilge ..	4	"	Bilge Planks' 50 2 1/2	5 x 4 1/2	"	
3rd Ditto	10 1/2	10 1/2	10	9	9 1/2	8 1/2	Bilge Planks	4 1/2	"	Ceiling in Flat	3 1/4	3 1/4	
Top Timbers	9	9 1/4	-	6 1/2	-	4 1/4	Bilge to Wales	4 1/4	"	Ditto Bilge to Clamp	4	"	
Deck } N° 26 Average } One over each hold beam	9	9	9	7 1/2	9	7 1/2	Wales 50 4 Strakes	5 1/4	5	Hold Beam Clamps. 3	5	4 3/4	
Beams }							Topsides 50 3	4 1/2	4	Deck Beam Ditto ..	5	4	
Deck Beams, length amidships 2 1/2	-	-	-	-	-	-	Sheer Strakes 50 3	4	"	Ceiling 'twixt Decks	2 3/4	2 1/2	
Hold } N° 24 Average } 4 1/2 feet	12 1/2	12 1/2	12 1/2	10 1/4	12 1/2	10 1/4	Plank Sheers	4	"	Hold Beam Shelves ..	2 1/2	"	
Beams }							Water } Upper Deck	10 x 6	-	Deck Beam Ditto ..	5 1/4	-	
Hold Beams, length amidships 2 1/4	-	-	-	-	-	-	Ways } Lower Deck	10 x 5 1/2	-				
Keel	14 1/2	14 1/4	14 1/2	-	-	-	Upper Deck	3 1/2	3 1/2				
Scarphs of Ditto .. 6 feet	16	15 1/4	16	-	-	-							
Keelsons													
Scarphs of Ditto .. 7 feet													
Size of Bolts in Fastenings distinguishing whether													

Her Masts, Yards, &c. are in ^{new} Good condition, and sufficient in size and length.

She has SAILS.		CABLES, &c.		ANCHORS, and their weights.		
N ^o .				Fathoms.	Inches.	N ^o . Weight.
	Fore Sails,	Chain				Bower,
	Fore Top Sails,	Hempen Stream Cable				
	Fore Topmast Stay Sails,	Hawser				Stream,
	Main Sails,	Towlines				
	Main Top Sails,	Warp				Kedge,
and		All of _____ quality.				

Her Standing and Running Rigging _____ sufficient in size and _____ in quality.

She has One Long Boat and three others

The present state of the Windlass is ^{new} Good Capstan Good Rudder new Good Pumps Two iron new

General Remarks and Statement and Date of Repairs, if any.

DATES of Surveys held while building, as per Section 35.	1st. When the Frame is completed	<u>27th January 1855</u>
	2nd. When the Beams are put in, &c.	<u>25th August</u>
	3rd. { When completed, and before the plank be painted or payed }	<u>23rd May 1856</u>

This vessel has been under my special survey while Building. Her frame, except two Sloom Timbers of Bantzin Oak, is English and African Oak - of good quality and well free from defects. The outside and inside Plank is well worked and free from defects. The Elm Plank of the Bottom is wrought to the height of Six feet three inches from the lower part of the keel. The vessel is additionally fastened by the introduction of 15 Pairs diagonal iron Plates 4 inches wide by $\frac{1}{2}$ inch thick extending from the upper side of the Mold Beams down across the Sloom ends - on the timbers, clenched on the Frame with iron Bolts. and with alternate Bolts of Yellow Metal thro outside and inside planking and clenched on the ceiling. Next the lower edge of the Sloom head Strakes inside on both sides is worked a Sister Nelson 12 inches Square and 9 feet in length of English and African Oak - thro Bolted in every Sloom. Poop. 56 feet long. 6 feet 7 inches deep. Forecastle 31 feet long 6 feet deep - all the requisitions of the Rules have been complied with. The vessel is well and substantially Built and is eligible to be Classed Nine Years Δ from 1857 -

Present condition of Caulking of Bottom, Good Deck, Good and Waterways Good

If Sheathed, Doubled, Felted, or Coppered. to be coppered in London When last done _____

I am of opinion this Vessel should be Classed 9 Years Δ from 1857

The Amount of the Fee.....£ 5 : 0 : 0 is received by me,

Mar 11

Special£ 30 : 13 : 0

Certificate£ : 5 : 0

Committee's Minute 10th March 1857

Character assigned Δ 9 Years

W. S. Smith



© 2021

Lloyd's Register Foundation