

REPORT of SURVEY for REPAIRS.

No. 111 Survey held at London Date 22nd January 1856
 on the Ship "Conflict" (of iron) Master Deas
 Tonnage 1305 Built at Liverpool When built 1855
1326
 By whom built Cato, Miller & Co Owners Smith J^r
 Port belonging to Liverpool Destined Voyage _____
 If Surveyed Afloat or in Dry Dock Union dry dock

Last Survey, No. 7411 Port Iron Ships Classed A

REPAIRS Now done :- 18 rivets renewed on Port side, and 22 on Starboard side, in various parts of the bottom - Two pairs of horizontal knees, on each side, fitted against the foremost bulkhead, which shewed symptoms of having worked slightly - The bottom has been cleaned, dried, and payed with two coats of red lead, and, subsequently, with two coats of a composition recently invented by Mr W. Wilson of Liverpool -

Present Condition of the

Decks	<u>good</u>	Transoms, Pointers, and Crutches	<u>good</u>	Windlass and Capstan	<u>good</u>
Waterways		Timbers of the Frame		Pumps	<u>4 in 11th</u>
Comings		Keelsons		Boats	<u>5</u>
Upper Deck Beams & Fastenings		Clamps and Shelves	<u>good</u>	Masts, Yards, &c.	<u>u</u>
Lower Deck Beams & Fastenings		Ceiling		Sails	<u>u</u>
Planksheers	<u>good</u>	Rudder		Anchors	No. of <u>3 B, 1 S, 2 K</u>
Sheerstrakes		Copper		Cables	<u>150 - 2 - 150 - 1 1/8</u>
Topsides		When put on		Hawsers and Warps	<u>13 x 9 x 1/2 x 6</u>
Wales				Standing & Running Rigging	<u>good & suff^{ce}</u>
Plating (Bottom) and Counter					

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good

This vessel is in a good and efficient state of repair, and having examined the ship, and compared her with the statement in the original Report, we are of opinion that she is eligible to be classed B dating from 1855

The Amount of Fee.....£ : : is received by me,

Special..... 3 : 3 : - 14/5/56

Certificate (if required) : :

Committee's Minute 16th May 1856

Character assigned B for 6 years from 1855

Charge £3 3 0

Number of years assigned to the Conflict to be expressed in the latter manner

Lloyd's Register Foundation

IRON432-0092