

# REPORT of SURVEY for REPAIRS.

Rec 8/11/58

No. 1500 Survey held at Glasgow Date 5<sup>th</sup> November 1858  
 on the Ann King Oporto Master A. Macdonald  
 Tonnage 208 Built at Penryn When built 1852+  
 By whom built J. B. Sherry & Co. Owners John Mitchell  
 Port belonging to Glasgow Destined Voyage St. de Camiers  
 If Surveyed Afloat or in Dry Dock Patent Slip

Last Survey, No. 1510 Port Glasgow Classed 9 A 1

## REPAIRS

Section 17, Ann Rule, Ceiling lifted, All oxidation on Plating removed, Renewed a few rivets in both sides  
 Hold Beams Doubled with Angle Iron 6 x 3 x 3/8 in, and an Additional one put in between Fore and Main Hatch, some Pillars renewed and the remainder refitted, Bulwarks repaired and Waterway Beams Caulked; Asphalted Bottom to Ribs and Punks, Ceiling replaced and some new  
 Re-coated with line of Red Lead and two Outside

## Present Condition of the

Decks	<u>Good</u>	Rivets	<u>Strong, some new</u>	Windlass and Capstan	<u>Good</u>
Waterways	<u>do</u>	Breasthooks and Stems	<u>Good</u>	Pumps	<u>2 Metal Copper</u>
Comings	<u>do</u>	Transoms, Pointers, and Crutches	<u>do</u>	Boats	<u>2 in etc Good</u>
Upper Deck Beams & Fastenings	<u>do</u>	Timbers of the Frame	<u>do</u>	Masts, Yards, &c.	<u>do</u>
Lower Deck Beams & Fastenings	<u>do</u>	Keelsons	<u>do</u>	Sails	<u>do</u>
Planksheers	<u>do</u>	Clamps and Shelves	<u>do</u>	Anchors	No. of <u>2 1/2 1 1/2 1 1/2 1 1/2</u>
Sheerstrakes	<u>Plating do</u>	Ceiling	<u>do</u>	Cables	<u>180 fathoms 1 1/2 in</u>
Topsides	<u>do do</u>	Rudder	<u>do</u>	Hawsers and Warps	<u>2 1/2 fathoms 6 1/2, 5, 4 1/2</u>
Wales	<u>do do</u>	Copper	<u>When put on</u>	Standing & Running Rigging	<u>Complete &amp; Good</u>
Plank (Bottom) and Counter	<u>do do</u>				

## General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. Part new & Good

This vessel has been surveyed in accordance with Section 17, Ann Rule and is now in a good and efficient condition fit for the safe conveyance of Dry and Perishable Cargo to and from all parts of the World and may continue as Clased

The Amount of Fee.....£ : : : is received by me,

*How*

Special..... 2 : 2 : :

Certificate (if required) : : 5 : :

Committee's Minute 9<sup>th</sup> November 1858

Character assigned 9 A 1



© 2019

Lloyd's Register Foundation

IRON433-0352