

2293

555

REPORT of SURVEY for REPAIRS.

and Change of Owners

No. ¹⁵⁴ Survey held at London Date 17th Sept^r to 20th Oct^r 1860
on the Iron S. "White Eagle" Master WilliamsTonnage 993 Built at Glasgow When built 1835By whom built _____ Owners RobinsonPort belonging to London Destined Voyage _____If Surveyed Afloat or in Dry Dock Nelson dry dock & East India dockLast Survey, No. 1236 Port Iron Classed G A 1
56

REPAIRS

The whole of the ceiling in hold and between decks removed and the inner and outer surfaces of the plating scraped and beaten likewise the frames & floor plates. The outer surface of plating of bottom we found to be much pitted varying from a 1/16 to 3/8 in bare, its in plating filled in with composition inside of plating good, rivet heads of garboard strakes & of the two strakes next above them wasted and now renewed about 3000 ke inside from middle line to bilge keelsons coated with Roman Cement above bilge keelsons with red lead, outside of plating coated with red lead and white line paint greater part of ceiling of hold below bilge keelsons now renewed, 2 strakes of deck next the waterways on each side from fore mast aft taken up and replaced, the one next waterway with E. Oak and second strake with Oregon pine, wood ass lining taken off, the main piece examined & found good, main & fore masts removed further aft, & decks recarved, new lower masts and Mizzen topmast, all new lower yards, 2 new spinnaker yards, and new topmast masts & other small spars

Present Condition of the

Decks	Goop	Freemails	Rivets. part new, good with PP	Windlass and Capstan	Goop
Waterways	do	Breasthooks and Stenson	do	Pumps 4 ho	do
Comings	do	Transoms, Pointers, and Crutches	do	Boats 5 ho	do
Upper Deck Beams & Fastenings	} do	Timbers of the Frame &	do	Masts, Yards, &c.	Most part new
Lower Deck Beams & Fastenings		Keelsons	do	Sails	part new Good
Planksheers	do	Clamps and Shells	do	Anchors No. of	3 B. 15 & 2 k
Sheerstrakes	do	Ceiling	good	Cables	Complete
Topsides	do	Rudder	do	Hawsers and Warps	Steam chain, Good
Wales	do	Copper	When put on	Standing & Running Rigging	do
Plank (Bottom) and Counter	do				

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. Good

This ship being at present in good order we are of opinion she may continue as Classed A 1

The Amount of Fee.....£ 1 : — : — is received by me,

Special ^{in extra} attend^{ance} 3 : 3 : —
Certificate (if required) : 5 : —

Committee's Minute 23rd November 1860Character assigned G A 1

second repair

Will: L. Davy
J. A. Martin



© 2019

Lloyd's Register
Foundation

IRON 434-0397