

REPORT of SURVEY for REPAIRS.

No. 174 Survey held at London Date 8th to 20th Mar 1861
 on the Iron Steamer "Pierfly" Master Nick
 Tonnage 502 Built at Liverpool When built 1854
 By whom built _____ Owners Genl & Co
 Port belonging to London Destined Voyage _____
 If Surveyed Afloat or in Dry Dock Upper Globe dry dock

Last Survey, No. 1923 Port Iron Classed C.A.1

REPAIRS

At present specially surveyed for Continuation in accordance with Iron Rules Sec 18. Outer and inner surfaces of plating of bottom scraped and all oxidation removed therefrom. Several planks of wood ceiling on each side removed and one plate of the iron ceiling on top of floors (the vessel being double bottomed to upper part of bilges) removed, likewise all plates over man holes in the same and the plating and rivets examined and found good. Local bunkers cleared and cleaned, the plating and rivets there good. Waterways scraped bright, examined & found good. Windlass unshipped. Linings removed. A main piece of new Pall Pitt of Iron Bark, an angle iron stringer introduced on Beam Ends in fore Tank $5\frac{1}{2} \times 3 \times \frac{1}{2}$ ins and secured to reverse angle iron on frames. a few rivets also there renewed. 5 planks of deck renewed with Yellow Pine. inner surfaces of plating where exposed coated with Red lead and bottom with black varnish

Present Condition of the

	Good	with RR	Good	with RR
Decks	do	do	Windlass and Capstan	do
Waterways	do	do	Pumps	3 ho do
Comings	do	do	Boats	3 ho do
Upper Deck Beams & Fastenings	do	do	Masts, Yards, &c.	do
Lower Deck Beams & Fastenings	do	do	Sails	2 suits do
Plank sheers	do	do	Anchors	No. of 3 B. 15 & 2 H
Sheerstrakes	do	do	Cables	270 fms good
Topsides	do	do	Hawsers and Warps	4 ho do
Wales	do	do	Standing & Running Rigging	do
Plank (Bottom) and Counter	do	do		

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways.

This vessel having at present been specially surveyed in accordance with Rule Sec 18 and being now in good condition we are of opinion she is eligible to be continued A1 for 3 years from 1860

The Amount of Fee.....£ 5 : — : — is received by me,

Special. usual 3 : 3 : —

Certificate (if required) : 5 : —

Committee's Minute 26th March 1861

Character assigned Cont^d 1 for 3 years from 1860

Will: C. Davey

J. Martin