

REPORT of SURVEY for REPAIRS.

No. 5 Survey held at London Date Dec. 28th 1861
 on the Iron B. "Haddington" Master G. Browne
 Tonnage 1459 Built at Liverpool When built 1846
 By whom built _____ Owners P. J. C. C.
 Port belonging to London Destined Voyage _____

If Surveyed Afloat or in Dry Dock Somes' Dry Dock, Green's Dry Dock & Co. J. Dock

Last Survey, No. 2032 Port Iron Classed 12 A 1 Con. 1/58 6y.

REPAIRS now done. The ceiling lifted in the flat of bottom from abate the main-mast to the fore-bulkhead, a great quantity of Asphalt found loose and blistered removed: the plating in way of the same scraped clean, about 500 rivets renewed, and inside flat of bottom coated with red-lead; Chain bolts renewed through Chocks fitted between the frames and an iron plate over the same rivetted to reverse frames. Tween decks coated with red-lead, Rudder-braces bushed, bottom scraped and coated with red-lead and Patent paint, rigger refitted and made good, Ceiling in flat replaced, and Deck partly Caulked.

Present Condition of the

Decks <u>good</u>	Treenails _____	Windlass and Capstan <u>good</u>
Waterways <u>"</u>	Breasthooks and Stemson _____	Pumps <u>"</u>
Comings <u>"</u>	Transoms, Pointers, and Crutches <u>Iron</u>	Boats <u>good & sufficient</u>
Upper Deck Beams & Fastenings <u>Iron</u>	Timbers of the Frame <u>good</u>	Masts, Yards, &c. <u>"</u>
Lower Deck Beams & Fastenings <u>where</u>	Keelsons <u>where</u>	Sails <u>"</u>
Planksheers <u>seen in</u>	Clamps and Shelves <u>seen</u>	Anchors No. of <u>"</u>
Sheerstrakes <u>good condition</u>	Ceiling _____	Cables <u>"</u>
Topsides _____	Rudder _____	Hawsers and Warps <u>"</u>
Wales _____	Copper _____ When put on _____	Standing & Running Rigging <u>"</u>
Plank (Bottom) and Counter _____		

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good where seen.

This vessel is now in good condition and in my opinion eligible to remain as Classed A1.

The Amount of Fee £ : : is received by me,

Special 2 : 2 : -

Certificate (if required) : 5 : -

Committee's Minute 19th April 1861

Character assigned Cont. 1/2

Charge for attendance £2..2



© 2019
 Lloyd's Register
 Foundation
 IRON435-0007