

2593

# REPORT of SURVEY for REPAIRS.

Rec 18/11/61

No. 17225 Survey held at Liverpool Date Sept 23 to Oct 24 1861  
 on the Grecian, New Stem, (2m) Master Sliver  
 Tonnage 1454 Built at Belfast When built 1861  
1555  
 By whom built \_\_\_\_\_ Owners Wibby & Co  
 Port belonging to Liverpool Destined Voyage Mediterranean  
 If Surveyed Afloat or in Dry Dock in Dry Dock & Afloat

Last Survey, No. \_\_\_\_\_ Port \_\_\_\_\_ Classed 12 A 1 3, 61

## REPAIRS

In consequence of having sustained damage, has had a great number of plates in the flat of the bottom, (which had been forced up by the vessel being on the ground) for about thirty five feet in length taken out, the keel in midships straightened, the iron plates that were taken out put in shape and replaced, two broken plates near the fore foot replaced with new, together with a large number of broken and started rivets, one iron coming and a part of the ceiling; and the bottom has been coated.

## Present Condition of the

Decks	<u>Good</u>	Treenails	<u>Pivots</u>	<u>Good</u>	Windlass and Capstan	<u>Good</u>
Waterways	"	Breasthooks and Stemson	"	"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	"	"	Boats	"
Upper Deck Beams & Fastenings	"	Timbers of the Frame	"	"	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	"	Keelsons	"	"	Sails	<u>well found</u>
Planksheers	"	Clamps and Shelves	"	"	Anchors	No. of 3 Bowers, Stem & Heads
Sheerstrakes	"	Ceiling	"	"	Cables	<u>well found</u>
Topsides	"	Rudder	"	"	Hawsers and Warps	<u>well found</u>
Wales	"	Copper	When put on	"	Standing & Running Rigging	<u>Good</u>
Plank (Bottom) and Counter	"					

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. done factory

Is in an efficient state, fit for the conveyance of dry and perishable cargoes with safety, to and from all parts of the world, and in my opinion should be continued as classed.

The Amount of Fee.....£ 3 : " : " is received by me,

Special.....4 : 4 : " 14/11/61

Certificate (if required) " : 5 : "

Committee's Minute 19th November 1861

Character assigned 12 A 1

record damage repairs

IRON435-0211



© 2019

Lloyd's Register Foundation



*Gucciarì 17225-*



© 2019

Lloyd's Register  
Foundation