

REPORT of SURVEY for REPAIRS.

No. 341 on the Iron S. "Vinefred" Master Tergent
 Survey held at London Date 30th Sept to 30th Nov 1861
 Tonnage 1359 Built at Chester When built 1854
 By whom built _____ Owners Sharples &
 Port belonging to Liverpool Destined Voyage Calcutta
 If Surveyed Afloat or in Dry Dock Mr Green's dry dock & E. & S. Dock

Last Survey, No. 1946 Port Iron. Classed A1
 First "No" 783 (IS)
 REPAIRS

All the ceiling removed to upper part of bilges and the composition of cement and gravel which was put in at Liverpool 2 years since proving inefficient and in a liquid state, except at extreme ends, now removed. a great number of rivets found wasted and the plating a little wasted or wasted off flat of bottom. 3150 rivets now renewed in edges and bulks. New bulkhead continued to upper deck 4 1/2 in thick trussed with angle iron 4 x 4 x 1/2 connected to side by frame & bracket knees. Bilge keelsons extended 40 ft at each end on each side 6 x 3 1/2 x 10/16. Coated inside and outside & the plating coated also inside with Portland cement new Hindlass English Oak & new Main Yard of Iron

Present Condition of the

Decks	Revised, part new	Good	New	Good
Waterways			Windlass and Capstan	
Comings			Pumps 2 no	do
Upper Deck Beams & Fastenings			Boats 6 no	do
Lower Deck Beams & Fastenings			Masts, Yards, &c. New Main Yd	do
Planksheers			Sails	do
Sheerstrakes			Anchors No. of 3 B. 1 S & 1 K	do
Topsides			Cables	Good
Wales			Hawsers and Warps	do
Plank (Bottom) and Counter			Standing & Running Rigging	Supp

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways.

This Vessel is now in good condition. The recommendations contained in our letter to the Committee of the 17th Oct^r have been complied with by the Owner and we now beg to submit her claims to the Committee for the A1 grade

The Amount of Fee.....£ 1 : - : is received by me,

Special.....5 : 5 : -

Certificate (if required) : :

Committee's Minute 24th January 1862.

Character assigned A1 for 9 Years

(H.S.B.)
 record separ



© 2019

Lloyd's Register
 Foundation

IRON435-0298