

REPORT of SURVEY for REPAIRS.

No. 18526 Survey held at Liverpool Date Nov-21-63 1863
 on the "Egyptian" Master Glover
 Tonnage 1986 Built at Belfast When built 1841
 By whom built Farland Owners Betty & Co.
 Port belonging to Liverpool Destined Voyage Mediterranean
 If Surveyed Afloat or in Dry Dock Sandon Graving Dock

Last Survey, No. 2520 Port Iron. Classed 12 A/61

REPAIRS

This Vessel was stranded on the Burto Bank, the 6th day of Nov^r 1863 which caused the undermentioned Plates to be indented. They were taken off and put in the Furnace the indentations taken out was examined and found perfectly free from defects.

One Plate 2nd Strake from Garboard (Port side) little aftside of Amidships, and one Plate in same strake opposite; also two Plates in 2nd Strake from Garboard and one in the 3rd from d^r (Starboard side) about forty feet forward from Amidships has been taken off & replaced; the Butt Straps to same and several Frame rivets renewed; twenty eight Butt Straps of outside Plating (Starboard side Amidships) and twelve Butt Straps (Port side) opposite recaulked, the Rudder Plates from one-half its length up from keel rivetted, the Coal Bunkers - both sides - repaired slightly, a portion of the Machinery repaired & renewed, and the bottom coated with composition.

Present Condition of the

Decks	Treenails	Windlass and Capstan
Waterways	Breasthooks and Stenson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Ditto Ditto at other places	Sails
Planksheers	Keelsons	Anchors No. of
Sheerstrakes	Clamps and Shelfs	Cables
Topsides	Ceiling	Hawsers and Warps
Wales	Rudder	Standing & Running Rigging
Plank (Bottom) and Counter	Copper When put on	

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways.

All satisfactory
 This Vessel is now in an efficient condition and fit for the conveyance of dry & perishable cargoes to & from all parts of the world and in my opinion should remain as Classed

The Amount of Fee.....£ 3 : " : " is received by me,

Special..... 2 : 2 : " 1/164

Certificate (if required) " : 5 : "

Committee's Minute 1st January 1864

Character assigned 12 A.1. Need Damage Repair



© 2019

Lloyd's Register Foundation

IRON437-0103

REPORT OF THE COMMITTEE ON THE

"
Captains" 1852



© 2019
Lloyd's Register
Foundation