

REPORT of SURVEY for REPAIRS.

& Continuation

in Book. No. 3 Survey held at (Northfleet) London Date Jan 6th to May 19th 1864
on the S^m "Pacific" Master
Tonnage $\frac{1469}{985}$ Built at London When built 1854
By whom built J. Scott Russell Owners F Chambers
Port belonging to London Destined Voyage
If Surveyed Afloat or in Dry Dock Victoria Dock & Northfleet dock

Survey, No. 2647 Port Iron. Classified 9 A 1 expired (2.3.62 62)

REPAIRS

Scraped bright both outside and inside, the wood beam ends bored and found good, the windlafs stripped (good) and chains examined -

Damage: eight fore hoods of plates on each side renewed also one piece of stem and one length of plate keel; three plates on starboard side renewed and five rerolled and refitted - On Port side, six plates renewed, and three rerolled, the after keel (broken) rewelded (three plates taken down to repair keel refitted) Four pairs of frames forward and three frames aft (broken) renewed -

Decay the garboard strakes nearly all rivetted Repainted with 2 coats of Red Lead

Present Condition of the

Decks	good	Treenails	Rivets	good	Windlass and Capstan	good
Waterways	do	Breasthooks and Stimson		do	Pumps	do
Comings	do	Transoms, Pointers, and Crutches		do	Boats	do
Upper Deck Beams & Fastenings	do	Timbers of the Frame at the openings		do	Masts, Yards, &c.	do
Lower Deck Beams & Fastenings	do	Ditto Ditto at other places		do	Sails	do
Planksheers	do	Keelsons		do	Anchors No. of	3 x 1 x 2
Sheerstrakes	do	Clamps and Shelves		do	Cables	examined good & sufficient
Topsides	do	Ceiling		do	Hawsers and Warps	do
Wales	do	Rudder		do	Standing & Running Rigging	do
Plank (Bottom) and Counter	do	Copper	When put on			

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways.

good

This vessel has now been Specially Surveyed in strict accordance with the rules, she is now in a good and efficient state of repair and is eligible in our opinion to be

The Amount of Fee.....£ 5: - - is received by me, continued A 1

Special..... 6: 6: -

Certificate (if required) - 5: -

from 1863

Committee's Minute 24th May 1864

Character assigned Cont A 1 for 5 years

& Expenses £4.13 (E.S. 14)

record damage repair

Lloyd's Register Foundation IRON437A-0017