

3652

REPORT of SURVEY for REPAIRS.

8846 Survey held at Birkenhead Date May 13 to July 1 1864
S. Abdul Medjid Master A. Reddie
400 Built at Glasgow When built 1854
 om built Laurie Owners Merron & Tell
 belonging to Glasgow Destined Voyage
 surveyed Afloat or in Dry Dock Great Float & Clavers Graving Dock
 ey, No. 2707 Port Iron Classed 12 A1 - 2, 62
not done (78601)

All the Ceiling in Hold & Trist decks
 timely removed, Windlass unhooked and wood lining
 taken off found good. Chains cable examined on deck
 and the Waternaps (E. & W.) scraped bright.

Fourteen Plates in flat of bottom and three plates
 in Bilge (Starboard side) also ten plates in flat of bottom (Port side)
 and nine Garboard plates (both sides) between Fore &
 Main Mast taken out and renewed and the whole
 of flat of bottom (both sides) from Fore to Main Mast
 scurvetted. The keels of several frames (amidships) renewed
 PTD

Condition of the					
Waterways	good	Treenails		Windlass and Capstan	good
Combs	"	Breasthooks and Stenson		Pumps	"
Upper Deck Beams & Fastenings	"	Transoms, Pointers, and Crutches		Boats	"
Lower Deck Beams & Fastenings	"	Timbers of the Frame at the openings		Masts, Yards, &c.	"
Plankshozers		Ditto Ditto at other places		Sails	well found
Sheerstrakes		Keelsons	good	Anchors No. of	3 B. 1. & 2. 16
Topsides		Clamps and Shelves		Cables	good & sufficient
Wales		Ceiling	"	Hawsers and Warps	"
Plank (Bottom) and Counter		Rudder	"	Standing & Running Rigging	"
		Copper	When put on		

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. Satisfactory

This vessel is now in an efficient state and fit for
 the conveyance of dry & perishable cargoes to & from all parts
 of the world and in my opinion - if the Committee see no objection -
 may be Classed A1 - 1864 - (See Owners letter requesting the same.)
 The Amount of Fee.....£ 1 : 0 : 0 is received by me, and marked E.S. or S.S. 1864

Special..... 6 : 6 : 0 7/14/64 AlmCertificate (if required) " : 5 : 0Committee's Minute Liverpool 8th July 1864Character assigned A1 S.S. - No 3 - 64Tell Wheeler

© 2019
 Lloyd's Register
 Foundation

IRGN437A-0081

3652 Iron

and the Butts of all Mousse frames on top of
have covering pieces now added, Rudder
hanging part renewed, the vessel cleanse
throughout and cemented (Portland) in flat of
the upper turn of keel; and the upper deck
Waterways caulked.

Ed Wheeler

Abigail & Medline



© 2019

Lloyd's Register
Foundation