

3832

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No. 2404** Survey held at Stockton last at W. Hartlepool Date 25th July, to 20th Oct. 1864
 Supplement on the Iron Screw Steamer "Myanga" Master E. W. W.
 Tonnage 1106 ⁴⁴/₁₀₀ Built at Stockton When built 1864
 By whom built Pearse Owners Chapple Button & Co.
 Port belonging to Liverpool Destined Voyage Mediterranean
 If Surveyed Afloat or in Dry Dock Afloat & in Dry Dock

Last Survey, No. 3082 Port Liverpool Classed A 1
6, 64

REPAIRS It was now had a Poop fitted, length 47 ft. 6 in from stern post. Frames let thro. gunwale stringers & scarfed down heads of main frames 3 ft. & rivetted to the same angle Irons 5 1/2 x 3 1/2 x 0/16. Side plating 6/16 single rivetted at edges double butt with 3/4 rivets. Beams double angle Irons 5 1/2 x 3 1/2 x 0/16 + 3 x 3 x 0/16. Plating of deck 3 in 1/2 Pine waterways of teak. Outside coated with paint, bottom with Mc. Junes Patent composition.

Tonnage below deck 1002.16
 Poop 74.74
 Deck House 29.54
 Gross 1106.44
 Engine Space 240.42
 Register 866.02

See Secretary's letter dated 27th July
 respecting Poop.

Present Condition of the

Decks	Greenails <u>Rivets</u>	Windlass and Capstan <u>Good</u>
Waterways	Breasthooks and Stemson	Pumps <u>Good</u>
Comings	Transoms, Pointers, and Crutches	Boats <u>Good</u>
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings	Masts, Yards, &c. <u>Good</u>
Lower Deck Beams & Fastenings	Ditto Ditto at other places	Sails <u>Good</u>
Planksheers	Keelsons	Anchors No. of <u>10. 8.0 with stock 23.00</u>
Sheerstrakes	Clamps and Shelves	Cables <u>300 fathoms of 1 9/16</u>
Topsides	Ceiling	Hawsers and Warps <u>Good</u>
Wales	Rudder	Standing & Running Rigging <u>Good</u>
Plating (Bottom) and Counter	Copper When put on	

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. Good

It is now in a good & efficient state and may in my opinion remain as now classed A 1

Messrs Chapple have been requested to forward the fee to the Town office.

The Amount of Fee.....£ - : - : is received by me,

Special..... 3 : 14 : 0 H.A. 8/11/64

Certificate (if required) : :

Committee's Minute 11th November 1864Character assigned A 1

© 2019

Lloyd's Register Foundation

IRON438-0013