

4022

**REPORT of SURVEY for REPAIRS.**

And Change of Owners.

No. in  
Reg. Book.

389

No. 19267 Survey held at Birkenhead & Date Jan<sup>ry</sup> 20 to March 18 65.

on the S. S. Shaftesbury Master J. Aitken

Tonnage  $\frac{680}{524}$  Built at Sunderland and When built 1862. 4 mo

By whom built Oswald Owners Wakefield &amp; Co.

Port belonging to Liverpool Destined Voyage Singapore.

If Surveyed Afloat or in Dry Dock Clayton's Woodside proving afloat.

Last Survey, No. 3153 Port Iron Classed 9 A 1.

REPAIRS now done. — A few rivets in bottom and in after part of Rudder renewed. bottom scraped and painted, one hold beam added. 3 Chasing beam pieces added in way of long hatch way at the upper and lower deck of bulb-iron  $7 \times \frac{7}{16}$  and double angle-iron of  $2\frac{1}{2} \times 2\frac{1}{2}$  on the upper part. — new fore & main-masts of iron in two plates in the round of  $\frac{9}{16}$  double riveted in butt and single in edges and 3 angle bars of  $4 \times 3 \times \frac{3}{16}$  in each. Topmasts and some other spars new and all the lower rigging now renewed of wire.

## Present Condition of the

Decks	partially Cambered	Treenails		Windlass and Capstan	good
Waterways	"	Breasthooks and Stemson		Pumps	"
Comings	good	Transoms, Pointers, and Crutches		Boats	good & sufficient
Upper Deck Beams & Fastenings	good	Timbers of the Frame at the openings	Iron	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	Iron	Ditto Ditto at other places	good	Sails	"
Planksheers	good	Keelsons	where	Anchors No. of	"
Sheerstrakes	where	Clamps and Shelves	seen	Cables	"
Topsides	seen	Ceiling		Hawsers and Warps	"
Wales		Rudder		Standing & Running Rigging	"
Plank (Bottom) and Counter		Copper	When put on		

General Observations and Opinion,

Caulking of Bottom, Deck, &amp; Waterways. good where examined.

This vessel is now in good condition and in my opinion eligible to remain as Classed 9 A 1.

The Amount of Fee.....£ 1 : " : " is received by me,

Special..... 2 : 2 : " 18/65 Wm

Certificate (if required) " : 5 : " "

Committee's Minute Liverpool 14<sup>th</sup> March, 1865

Character assigned 9 A 1 - Record Change of Owners

JK



© 2019

Lloyd's Register  
Foundation

IRON-438-0177



*"Shaftesbury" 19267*



© 2019

Lloyd's Register  
Foundation