

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 452 Survey held at London. Date 4th to 29th July 18 65.
 on the Iron Ship "John Rennie" Master J. E. Jagg.
 Tonnage 848 Built at London. When built 1863.
 By whom built Rennie Owners East & Co. J. J. Jagg.
 Port belonging to London Destined Voyage Hong Kong.
 If Surveyed Afloat or in Dry Dock Union Dry Dock.
 Last Survey, No. 3385 Port Iron. Classed 13. A. 1.
 63

REPAIRS

Now done:-

About eight hundred Rivets in the Bottom, cut out and renewed, in consequence of their points, having been eaten some distance within the outside surface of the Bottom plating.

Payed the Bottom with one coat of boiled oil, three coats of paint, and one coat of Gallon.

The original Hold and between deck Beams Stations, which were two inches in diameter, replaced by others three inches in diameter.

Present Condition of the

Decks		<u>Rivets</u> <u>Renewed</u>		Windlass and Capstan	
Waterways		Breasthooks and Stemson		Pumps	<u>Good</u>
Comings	<u>Good</u>	Transoms, Pointers, and Crutches	<u>Good</u>	Boats	
Upper Deck Beams & Fastenings		Transoms of the Frame at the openings		Masts, Yards, &c. <u>By inquiry and</u> <u>Condition, now ascertained.</u>	<u>and</u>
Lower Deck Beams & Fastenings	<u>Good</u>	Transoms Ditto at other places	<u>where</u>	Sails	<u>sufficient</u>
Planksheers		Keelsons		Anchors No. of	<u>where</u>
Sheerstrakes	<u>Scraped and</u>	Clamps and Shelves	<u>seen</u>	Cables	
Topsides	<u>painted.</u>	Ceiling		Hawsers and Warps	<u>seen</u>
Wales		Rudder		Standing & Running Rigging	
Plank (Bottom) and Counter	<u>painted</u>	<u>Copper</u> <u>paint</u> When put on <u>now</u>			
General Observations and Opinion,		Caulking of Bottom, Deck, & Waterways.	<u>Good where seen.</u>		

She is now in good and efficient condition, and fit, in our opinion, to remain as Classed: Voy 13. A. 1.

The Amount of Fee.....£ : : is received by me,

Special..... 2 : 2 : 0

Certificate (if required) : 5 :

Committee's Minute 2nd October 18 66

Character assigned 13 A 1
Record repair MT

IRON 440 - 0090



© 2019

Lloyd's Register
Foundation