

REPORT of SURVEY for REPAIRS.

Rev 24/10/66

No. in Reg. Book. **No. 20219** Survey held at Liverpool Date 28th June to 2 Aug^r 1866
 on the Iron Bt "Ismay" Master Campbell
 Tonnage 422 Built at Glasgow When built 1861-4 mo
 By whom built Stephens Owners Ismay & Co
 Port belonging to Liverpool Destined Voyage South America
 If Surveyed Afloat or in Dry Dock Brunswick graving dock & Afloat

Last Survey, No. 4031 Port Iron Classed A 1
S S No 1. 65

REPAIRS

Through damage sustained
 On the Starboard and Port sides, two bulwark plates, fore plates of sheerstrake and two next courses below it, new stem scarphed at upper end, new cutwater plating and keel rails, one angle iron beam to monkey fore-castle and the remainder straightened, new deck to monkey fore-castle, two catheads new, both Hawse pipes new, three chain plates repaired and rivetted, fore shafts of main and topgallant Rails new. Bowspit new of iron, plates 7/16 ins, 4 angle irons 3 1/2 x 3 1/2 x 7/16. Edges single rivetted, butts double rivetted, new sibboom of Pine

Present Condition of the

Decks	} Good	Transoms	} Good	Windlass and Capstan	} Good
Waterways		Breasthooks and Stemson		Pumps	
Comings		Transoms, Pointers, and Crutches		Boats	
Upper Deck Beams & Fastenings		Timbers of the Frame at the openings		Masts, Yards, &c.	
Lower Deck Beams & Fastenings	} and	Ditto Ditto at other places	} and	Condition, how ascertained	} and
Planksheers		Keelsons		Sails	
Sheerstrakes 2 plates new		Clamps and Shelves		Anchors No. of	
Topsides 4 do do		Ceiling		Cables	
Wales	} firm	Rudder	} Suff	Hawsers and Warps	} Suff
Plank (Bottom) and Counter		Copper — When put on		Standing & Running Rigging	

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. Good

She is now in good condition and eligible in my opinion to continue as Classed A 1

The Amount of Fee.....£ / : " : " is received by me,

Special..... / : / : " 19/10/66

Certificate (if required) " : " : "

Committee's Minute Liverpool, 23rd October 1866

Character assigned A 1. Record Damage Report

Special Damage £ 42 40 9d 19/10/66



© 2019

Lloyd's Register Foundation

IRON 440-0117

"Is may"
-20219-



© 2019

Lloyd's Register
Foundation