

REPORT of SURVEY for REPAIRS.

No. in 7. Book. **No.** 29 Survey held at London Date Sept 8 to Oct 8 1866
 on the Iron Screw Steamer "Typhoe" Master J Douglas
 Tonnage 698 Built at Sunderland When built 1860
 By whom built _____ Owners H Taylor
 Port belonging to London Destined Voyage Newcastle
 If Surveyed Afloat or in Dry Dock Bowfreck & Thames Iron Works Dry Dock

Last Survey, No. 4573 Port Iron Classed 9 A. 1. (C. S. 66) 1st

REPAIRS now done in consequence of Damage,

Four fore hood plates on the Starboard and three on the Port side, below the hawsepipes, renewed; Two broken frames on each side forward doubled with angle iron the size of the frames rivetted to them and to the outside plating, and two on the Starboard side with four feet lengths of angle iron fitted in the throat: the Stem scarphed about four feet from the head: several bent plates taken down, made fair and replaced, a few slack rivets in the fore body renewed and several butts caulked; - The windlass unhung and
 I.P.O.

Present Condition of the

| Decks | Greenails | Rivets | Windlass and Capstan |
|-------------------------------|-----------|--------------------------------------|----------------------------|
| Waterways | } good | Breasthooks and Stemson | } good |
| Comings | | Transoms, Pointers, and Crutches | |
| Upper Deck Beams & Fastenings | | Timbers of the Frame at the openings | |
| Lower Deck Beams & Fastenings | } where | Ditto Ditto at other places | } where |
| Planksheers | | Keelsons | |
| Sheerstrakes | | Clamps and Shelves | |
| Topsides | } seen | Ceiling | } seen |
| Wales | | Rudder | |
| Plank (Bottom) and Counter | | Copper | |
| | | Paint When put on | standing & Running Rigging |

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good where seen

She is now in good condition, fit in my opinion to remain as classed. 9 A. 1.

The Amount of Fee.....£ : : is received by me,
 Special..... 2 : 2 :
 Certificate (if required) : :
 Committee's Minute 19th October 1866
 Character assigned 9 A. 1. M. K.
Damage £ 5-5-

H. J. Cornish



© 2019

Lloyd's Register Foundation

IRON 440-0125

5/15 Iron

the linings renewed, the main piece good; and
The outside surface of the plating painted
with Red lead. —



© 2019

Lloyd's Register
Foundation