

REPORT of SURVEY for REPAIRS.

& Dec 5th 5th

No. 5186 Survey held at London Date Oct^r 21st Nov^r 1865.
Barque Star of the West Master George Ellery.
 Tonnage 387 Built at Sunderland When built 1865.
 By whom built W. Pile Owners Pardew & Co.
 Port belonging to Plymouth Destined Voyage Algoa Bay.
 If Surveyed Afloat or in Dry Dock "Nelson" Pat^l Slip.

Survey, No. 5186 Port Iron Classed A. 1.
Previous Report.

from damage received by getting ashore in a gale of wind
 Algoa Bay (see report) Cut out four plates found damaged on the
 side in the bottom and two on the Port. - Two new plates introduced
 on the starbd, and repaired two, also two on the Port side, and renewed
 about four hundred rivets, and double the number or more on the starbd
 side, found started, loose, disturbed &c. Repaired one of the Ribs.
 fitted a double angle iron stringer, 20 ft long, 3 x 3 1/2 in over the damaged
 part (both sides) in the flat of bottom, as compensation, or to prevent her being
 forced any more out of form at that part of it. Caulked and overhauled
 all butts found disturbed, and put the plating, ribs &c all in order as far
 as practicable, fitted a new whelp, and box to windlass. Refitted steering gear,
 gave new lights to the side, repaired the Cement, also the Ceiling, relaid it &c
 painted the inside and outside, with red lead and other paint. - and supplied
 her with 60 fathms of 1 3/8 Chain tested up to 34 Tons. at our public
 proving house }
 new or in good order

	Freehold	Rivets	good	Windlass and Capstan	in good order
Waterways	"	Breasthooks and Stemson	"	Pumps	"
Decks	"	Transoms, Pointers, and Crutches	"	Boats	"
Deck Beams & Fastenings	"	Timbers of the Frame at the openings	"	Masts, Yards, &c.	"
Deck Beams & Fastenings	"	Ditto Ditto at other places	"	Condition, how ascertained, from the Deck	"
Keelsons	"	Keelsons	"	Sails	"
Clamps and Shelves	"	Clamps and Shelves	"	Anchors No. of 2.	"
Ceiling	"	Ceiling	"	Cables (60 fms new as per Cert ^{ts})	"
Rudder	"	Rudder efficient	"	Hawsers and Warps	"
Copper	"	Copper	"	Standing & Running Rigging	"
When put on		When put on			

Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good.

I am of opinion she is entitled to remain
 as class'd A. 1.

Samuel P. Jones

Amount of Fee.....£ / : : is received by me,

Special..... / : / :

Certificate (if required) : :

Committee's Minute 18

Inspector assigned



© 2019

Lloyd's Register
 Foundation

IRON 440-0795