

5579  
Damage Repair, -  
2593

**REPORT of SURVEY for REPAIRS.**

No. in Book. **No.** 36 Survey held at London Date 22<sup>nd</sup> May to 7<sup>th</sup> June 1867  
on the Iron Screw "Thames" Master John Pinkerton  
Tonnage 1376 Built at Sunderland When built 1864. (4. Mo.)  
By whom built Oswald Owners Temperley & Co.  
Port belonging to London Destined Voyage Quebec  
If Surveyed Afloat or in Dry Dock Thames graving dock

ast Survey, No. 4191 Port IRON Classed A. 1.  
REPAIRS 6. 65

Now done in consequence of damage:- On the Port-side, -  
Renewed two plates, just below the water-line aft, and repaired four  
frames. - put out seven plates in various places along the side,  
set them to form, also the frames in the way of them where bent,  
re-riveted and caulked them. - Replaced the fishing and  
cabin-fixtures which have been removed for the performance  
of the above. -

Payed the Bottom with one of Paint and one of Ballon.  
She was cemented in the Bottom when built. -

A large number of the Butts of the Bottom-plating, on both  
sides, recaulked, and renewed several slack Rivets in the  
Stem. -

Present Condition of the

Decks		Rivets.		Windlass and Capstan	
Waterways	Good	Breasthooks and Stemson	Good	Pumps 4 No.	Good where seen.
Comings		Transoms, Pointers, and Grutches		Boats 5	
Upper Deck Beams & Fastenings	where	Timbers of the Frame at the openings	Four repaired some others bent straight	Masts, Yards, &c.	By inquiry & observation
Lower Deck Beams & Fastenings		Ditto Ditto at other places		Condition, how ascertained	
Plank sheers	seen	Keelsons	Good	Sails	Good and
Sheerstrakes		Clamps and Shelves		Anchors No. of 3 B. 15. 2 K.	
Topsides	Painted	Ceiling	seen	Cables	sufficient
Wales Two plates ren.		Rudder		Hawsers and Warps	
Plank (Bottom) and Counter		Copper Paint When put on	205	Standing & Running Rigging	where seen.
General Observations and Opinion,		Cemented in Bottom in 1864.		Good where seen.	
		Caulking of Bottom, Deck, & Waterways.			

She is now in good and efficient condition,  
and fit, in my opinion, to remain classed. A. 1.

The Amount of Fee.....£ 3 : - : } is received by me.  
Special..... 1 : 1 : }  
Certificate (if required) - : - : }  
26/6/67

Committee's Minute 28<sup>th</sup> June 18 67  
Character assigned A 1

Damage Survey  
fee - £ 3.3.0

record damage report