

# REPORT of SURVEY for REPAIRS.

Rec 16/7/67

No. in Reg. Book. **No. 2659** Survey held at Wagon Date 29th June 1867  
 on the Ann S. Osborn Master ✓  
 Tonnage 482 Built at Wagon When built 1866  
 By whom built Alfred Stephen & Son Owners Cumming & Co  
 Port belonging to London Destined Voyage China  
 If Surveyed Afloat or in Dry Dock Alfred Stephen & Son Patent Slip

Last Survey, No. 4825 Port Iron Classed A1

**REPAIRS** Fitted with Awning Deck from After part of Monkey  
 Forecastle to Aft side of Main Rigging; Frames 3 x 3 x 5/16 extended in  
 a rounded form from Forecastle to Aft. Spaced about 3 feet apart.  
 Plate on side 15 x 5/16 with an extra plate in way of Rigging 19 x 5/16  
 side supported with 1 1/2 in Spur about 4 ft 9 in apart.  
 Aft Plate Outside Hatchway 9 x 5/16, Yellow Pine Deck 2 1/2 x 14 1/2 in  
 through fastened with Galvanized Nut & Screw Bolt, Side Pits and  
 Louvers left open on Main Deck as originally fitted, Stanchions to  
 Awning Deck 2 1/4 in to each Beam

## Present Condition of the

Decks	<u>New</u>	Nails	<u>New</u>	Windlass and Capstan	<u>New</u>
Waterways	<u>do</u>	Breasthooks and Stemson	<u>do</u>	Pumps	<u>do</u>
Comings	<u>do</u>	Transoms, Pointers, and Crutches	<u>do</u>	Boats	<u>do</u>
Upper Deck Beams & Fastenings	<u>do</u>	Timbers of the Frame at the openings	<u>do</u>	Masts, Yards, &c.	<u>do</u>
Lower Deck Beams & Fastenings	<u>do</u>	Ditto Ditto at other places	<u>do</u>	Condition, how ascertained	<u>from Examination</u>
Planksheers	<u>do</u>	Keelsons	<u>do</u>	Sails	<u>New</u>
Sheerstrakes	<u>do</u>	Clamps and Shelves	<u>do</u>	Anchors No. of	<u>31 3/4 1 Star 2 Wedge</u>
Topsides	<u>do</u>	Ceiling	<u>do</u>	Cables	<u>Complete</u>
Wales	<u>do</u>	Rudder	<u>do</u>	Hawsers and Warps	<u>do</u>
Plank (Bottom) and Counter	<u>do</u>	Copper	<u>✓</u> When put on <u>✓</u>	Standing & Running Rigging	<u>do</u>

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways.

As in good and efficient condition, eligible in my opinion to remain as classed

The Amount of Fee.....£ 4 : 0 : 0 is received by me,

Special..... 6 : 6 : 0

\* Certificate (if required) : 5 : 0

Committee's Minute 16th July 1867

Character assigned A1

"Awning deck"

Lloyd's Register  
Foundation

IRON441-0069