

6219

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No. 3744** Survey held at Hull Date May 16th 1867
on the Iron Steamer Albion Master Dossor
Tonnage 966 Built at Hull When built 1861
By whom built Samuelson Owners Wilson & Co / Clouston, Rotten
Port belonging to Hull Destined Voyage Gothenburgh London
If Surveyed Afloat or in Dry Dock On cables slip-way afloat in Victoria & Railway Docks & on hard at
Custom House Dimensions Length 245.2 & Breadth 29 - Depth 17 ft -

Last Survey, No. 4763 Port Iron. Classed 9 A 1
(8362) 12.65

REPAIRS

How done - The Engines & Boilers renewed - The ceiling in holds lifted and the surfaces of plating out and inside scraped clean several rivets renewed in the bottom (inch 3/4), the bottom cemented & the ceiling partly relaid & renewed - Three lengths of waterway renewed with red pine and several lengths of deck plank in way of new Boilers, 57 feet in length on each side of bulwark removed & replaced with iron - One inner strake of plating at bilge doubled for about 85 feet in length on each side with T8 plates - Butts strapped & double rivetted Deck Caulked. Bottom outside coated with Tar & the Black leaded the remainder coated with Paint.

How fitted - House for Passengers 814.84
Store Locker 115.99
1.27

Allowance for Piping Power 966.36
194.11
Register 772.25

Present Condition of the

Decks	Greenalls	Windlass and Capstan
Waterways	Breasthooks and Stemson	Pumps
Comings	Transoms, Pointers, and Crutches	Boats
Upper Deck Beams & Fastenings	Timbers of the Frame at the openings	Masts, Yards, &c.
Lower Deck Beams & Fastenings	Ditto Ditto at other places	Condition, how ascertained
Planksheers	Keelsons	Sails
Sheerstrakes	Clamps and Shelves	Anchors No. of
Topsides	Ceiling	Cables
Wales	Rudder	Hawsers and Warps
Plank (Bottom) and Counter	Copper	Standing & Running Rigging

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways.

Efficient.

Is in good condition & eligible in my opinion to remain as classed A 1 & marked (to 67)

The Amount of Fee.....£ 2: - :

Special..... 4: 4:

Certificate (if required) :

Committee's Minute

Character assigned

Damage returned back Quater £ 2. 2/- 10

18

Thosy verbally requested
by Wm. (Chas) Wilson WD

Lloyd's Register
Foundation

IRON442-0188