

Iron ~~6242~~ *6243* *Triennial Survey* *29203*
REPORT of SURVEY for REPAIRS.

No. in Reg. Book. *No.* *5612* Survey held at *London* Date *April 25th to May 16th / 60.*
P64 on the *Iron B^{te} "Sunbeam"* Master *E. Lovell*
 Tonnage *442* built at *Kirkcaldy* When built *1857.*
 By whom built _____ Owners *Duncan*
 Port belonging to *London* Destined Voyage *Madras*
 If Surveyed Afloat or in Dry Dock *Bridge dry Dock and East India St^{cs}*

Last Survey, No. *5612* Port *Iron.* Classed *12. A. 1 (Y. 67.)*
 REPAIRS *Now done as per Sec 19.* (T.S. 65.)

The timber boards, and equal to one strake of ceiling removed all fore and aft on each side, with both surfaces of outside plating exposed, except inside ~~and~~ under the Cement; and found the frames, floor-plates beams, stringers and plating, also Rivets &c, in good condition, and the Cement satisfactorily adhering to the iron.

The bottom paved with two coats of Lime, and one of tallow composition; the topsides and the whole of the iron work inside painted.

Renewed nearly two thirds of the upper deck with yellow pine, being principally in the waist on each side.

Present Condition of the

Deck upper, about <i>2/3rd</i> new	<i>Good where seen</i>	Upper Rivets	<i>Good where seen</i>	Windlass and Capstan	
Waterways		Breasthooks and Stenson		Pumps <i>3</i>	
Comings		Transoms, Pointers, and Crutches		Boats <i>3</i>	
Upper Deck Beams & Fastenings		Timbers of the Frame at the openings		Masts, Yards, &c. <i>Good</i>	
Lower Deck Beams & Fastenings		Ditto Ditto at other places		Condition, how ascertained <i>insp^d and enquiring</i>	
Planksheers		Keelsons		Sails	
Sheerstrakes		Clamps and Shelves		Anchors No. of <i>3 B. 18. 2</i>	
Topsides		Ceiling		Cables	
Wales		Rudder		Hawsers and Warps	
Paint (Bottom) and Counter		Copper <i>Paint</i> When put on <i>Now</i>		Standing & Running Rigging	
General Observations and Opinion,		Caulking of Bottom, Deck, & Waterways. <i>Good where seen.</i>			

She is now in good and efficient condition, and fit in my opinion to remain as Classed *Vin A. 1.* and to be marked in the Register (T.S. 1860). — On the 16th Inst an order was left at this office requesting her to be marked in the Register in the *A* grade, this I beg to submit to the

The Amount of Fee.....£ — : — : is received by me, Committee's consideration

Special.....*3-3-0*

Certificate (if required) *5/-*

Committee's Minute *19th May* 18 *60.*

Character assigned *A 1* T.S. 18 *60*



© 2019

Lloyd's Register Foundation

IRON 442 - 0211