

REPORT of SURVEY for REPAIRS.

in Register

No. 239

No. 3836

Survey held at

Hull

Date

May 19th

1868

on the

Iron Steamer Don Antonio

Master

Ribeiro

Tonnage

1178

Built at

St Glasgow

When built

1860

By whom built

Hill

Owners

Barley & Co

Port belonging to

Lisbon

Destined Voyage

Lisbon

If Surveyed Afloat or in Dry Dock

on No 1 Slipway & afloat in Victoria Dock

Last Survey, No.

5239

Port

Iron

Classed

B 1

REPAIRS

M.C. 60 R.p. 165 H. 66

S.S. 42 3. 66

12. 66

Now done - The bottom cleaned and coated with Paint. Boiler removed and the vessel examined under the same and the asphalts repaired where required. New Boiler supplied. Roop extended forward for 42 feet covering Engine Space. The alternate frames being carried across & forming beams, angle iron $4\frac{1}{2} \times 3 \times \frac{1}{2}$ b. plating $\frac{1}{2}$ b. Single rivetted at Butts & Edges rivets $\frac{3}{4}$, the plates extended forward to the front of the Roop. The main deck in way of the Boiler & new part of Roop properly shifted & replaced with Yellow Pine and caulked. New fore lengths of Roop Waterway of Lead

Tonnage Under Deck 981. 11

Roop - 169. 83

House for Passengers 27. 89

Engine Room 1178. 83

377. 23

801. 60

Present Condition of the

Decks

Waterways

Comings

Upper Deck Beams & Fastenings

Lower Deck Beams & Fastenings

Planksheers

Sheerstrakes

Topsides

Wales

Plank (Bottom) and Counter

Fastenings

Breasthooks and Stemson

Transoms, Pointers, and Crutches

Timbers of the Frame

Keelsons

Clamps and Shelves

Ceiling

Rudder

Copper

When put on

Windlass and Capstan

Pumps

Boats

Masts, Yards, &c.

Sails

Anchors No. of

Cables

Hawsers and Warps

Standing & Running Rigging

General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways.

Is eligible in my opinion to remain as classed B 1
Cemented 12. 66 - Space under Boiler previously asphalting

The Amount of Fee.....£ 3 : - : -

is received by me,

Davidson

Special.....

Certificate (if required)

Committee's Minute

2nd June

1868

Character assigned

B 1



© 2019

Lloyd's Register Foundation

IRON442-0225