

No 1 Survey REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 205 on the Iron S.S. "Berrington" Master R. Baker Survey held at London Date Aug. 22nd to 27th 1868
 Tonnage 629 built at Newcastle When built 1865
 By whom built Palmer Owners H. Morton
 Port belonging to Sunderland Destined Voyage Sunderland
 If Surveyed Afloat or in Dry Dock Pontons, Victoria Dock

Last Survey, No. 4729 Port Iron. Classed A. 1
 66

REPAIRS

Now done, The bottom scraped and painted with two coats of Red lead and one of zinc and tallow. This vessel is fitted in the holds with water ballast tanks; the man hole doors have been removed, and a strake of ceiling lifted at the bilges, fore and aft. All where seen proved satisfactory; the inside surface of the plating, frames, &c have been recently painted and are in good condition - the port side of the windlass stripped and new linings fitted; about 20 keel rivets and 40 of the bottom renewed, the rudder braces rebushed and about 45 butts of the bottom caulked -

Present Condition of the

Decks		Transoms	Rivets	Windlass and Capstan	good
Waterways	good	Breasthooks and Stemson	good	Pumps	
Comings		Transoms, Pointers, and Crutches		Boats	two and
Upper Deck Beams & Fastenings		Timbers of the Frame at the openings		Masts, Yards, &c.	efficient
Lower Deck Beams & Fastenings		Ditto Ditto at other places	where	Condition, how ascertained	by observation from deck
Planksheers	scraped & painted	Keelsons		Sails	good
Sheerstrakes	do	Clamps and Shelves		Anchors	No. of 3 B. 15 2 R. and
Topsides	do	Ceiling	seen	Cables	
Wales	do	Rudder		Hawsers and Warps	sufficient
Plank (Bottom) and Counter	scraped and painted	Copper	Asp	Standing & Running Rigging	
General Observations and Opinion,		Caulking of Bottom, Deck, & Waterways.	good where seen		

She is now in good and efficient condition, fit in my opinion to remain as classed A. 1. and to be marked in the

The Amount of Fee.....£ - : - : is received by me, Register (S.S. No. 1. 68)

Special.....2 : 2 :

Certificate (if required) : : :

Committee's Minute 25 September 1868

Character assigned

A. 1

S.S. No. 1-18 WAS



© 2019

Lloyd's Register Foundation

IRON443-0014