

# REPORT of SURVEY for REPAIRS.

No. in Reg. Book. **No.** 448 Survey held at London Date 14<sup>th</sup> Oct<sup>r</sup> 28<sup>th</sup> 1868  
 on the Iron Sch<sup>r</sup> Prince of Wales Master J. Sutherland.  
 Tonnage 238 built at Aberdeen When built 1845.  
 By whom built — Owners Mackay &  
 Port belonging to London Destined Voyage Brisbane.  
 If Surveyed Afloat or in Dry Dock Regent dry dock & East India Docks  
Change of Owners.  
 Last Survey, No. 4640 Port Iron. Classified A. 1. ss No 3 in 68  
66

## REPAIRS

Survey'd in ballast.

Scraped and Clean'd, and beat off all oxidation found outside. Dreg'd the deck bright, pieced or repaired and Caulked it. Condenn'd the Pawl, also the Garrick bits found decay'd. introduced New Pawl, and new Garrick bits of English oak. New Knees, and refitted the windlass. — Three new lengths of rough tree rail fitted on the Port side, and four Stations. new transporting block on the Port bow rail, wood work to the Stern, and all in connection with the Steering wheel, lining, timbers &c all new. Masts. Spars & scraped clean, and examin'd, defect removed from the Foremast, new Crops trees fitted, and the rigging put all in order, or made good and efficient. Coated the outside with red lead and other paint. —

## Present Condition of the

Decks	<u>good</u>	Trunnels	<u>bolts where seen good</u>	Windlass and Capstan	<u>in good order</u>
Waterways	"	Breasthooks and Stenson	"	Pumps	"
Comings	"	Transoms, Pointers, and Crutches	"	Boats	"
Upper Deck Beams & Fastenings	<u>firm</u>	Timbers of the Frame at the openings	"	Masts, Yards, &c.	"
Lower Deck Beams & Fastenings	"	Ditto Ditto at other places	"	Condition, how ascertained	"
Planksheers	"	Keelsons	"	Sails	"
Sheerstrakes	"	Clamps and Shelves	"	Anchors No. of <u>3</u>	"
Topsides	"	Ceiling	"	Cables	"
Wales	"	Rudder	<u>efficient</u>	Hawsers and Warps	"
Plank (Bottom) and Counter	"	Copper	When put on	Standing & Running Rigging	"

## General Observations and Opinion,

Caulking of Bottom, Deck, & Waterways. good.

She appears now in good condition, and has been overhauled outside, also inside as far as practicable. — — I am of opinion she is entitled to remain as class'd A. 1.

The Amount of Fee.....£ 1 : — : } is received by me,  
 Special..... 2 : 2 : }  
 Certificate (if required) : 5 : }

Samuel Pearson

Committee's Minute

1<sup>st</sup> January 1869

Character assigned

A 1



© 2019

Lloyd's Register

Foundation

IRON443-0251