

REPORT of SURVEY for REPAIRS.

No. in Reg. Book. 294 No. 1359 Survey held at London Date, first Survey 5th Sept Last Survey 6th Nov 1869
 on the iron ship "Winifred" Master Loftus
 Tonnage 1359 built at Chester When built 1855
 By whom built Sharpley Owners Sharpley
 Port belonging to Liverpool Destined Voyage Sydney
 If Surveyed Afloat or in Dry Dock Sharnes Iron Works Graving Dock and Afloat

Last Survey, No. 6372 Port Iron Classed A1
 REPAIRS, &c. Es. 68 Cent. 64 5/8 6. 68

Hold cleared, proper stages made both inside and outside; the whole of the ceiling inside removed, vessel chipped and beaten clean throughout, plank sheers and waterways scraped bright, plating drilled in sundry places, and found to be fully up to its original thickness. Windlass unhung, wood linings stripped, and chain cables ranged on deck for examination.

Some part of the butts of the bottom plating around the Bilges repaired and caulked; one plate on Starboard in upper course of bottom renewed 1/2 thick. Windlass renewed of Oak, and a large proportion of the ceiling in lower hold of Pitch and Red Pines. Steering gear refitted, and part new, all fastenings to chain and preventer. Plates replaced with new. Cement coating repaired. Inside painted from middle line to gunwale, excepting the lower deck beams they being coated only in way of the stringer plates bottom coated with Mc. Luning's composition.

Present Condition of the	Decks	Waterways	Comings	Upper Deck Beams & Fastenings	Lower Deck Beams & Fastenings	Plank sheers	Sheerstrakes	Topsides	Wales	Plank (Bottom) and Counter	Engine Room Skylights	Coal Bunker, Openings, Lids, &c.	General Observations and Opinion,
3 Good	3 Good	3 Good	3 Good	3 Good	3 Good	3 Good	3 Good	3 Good	3 Good	3 Good	3 Good	3 Good	3 Good

Is now in good and efficient condition, fit for the safe conveyance of dry and perishable cargoes, to and from all parts of the World, and in our opinion eligible to be Classed A1 and be marked 1. S. A. 3. 69.

The Amount of Entry Fee.....£3 : - : is received by me.

Special.....£5 : 5 : 0

Certificate (if required) : 5 : 0

Committee's Minute 11th November 1869

Character assigned B

W. H. Eastlake
J. H. Eastlake



© 2019
 Lloyd's Register
 Foundation

IRON 445-0105